

A.D-A250 057

RECONNAISSANCE

GENERAL-Im-C

①

# RECONNAISSANCE REPORT

## FLOOD CONTROL AND OTHER WATER-RELATED PURPOSES

WYACONDA RIVER BASIN,  
MISSOURI AND IOWA

DTIC

ELECTE

MAY 2 1992

S C D

DECEMBER 1991

92-12056



US Army Corps  
of Engineers  
Rock Island District

DISTRIBUTION STATEMENT A

Approved for public release;  
Distribution Unlimited

REVISED MARCH 1992

92 5 04 126

**A250 067**

# **CONNAISSANCE REPORT**

## **FLOOD CONTROL AND OTHER WATER-RELATED PURPOSES**

### **WYACONDA RIVER BASIN MISSOURI AND IOWA**

DTIC  
ELECTRONIC  
MAY 8 1985

S

C

**DECEMBER 1991**



**US Army Corps  
of Engineers**  
Rock Island District

DATE	FROM	STATE	NEA
12/21/91	11:20		

**REVISED MARCH 1991**


**Best  
Available  
Copy**

CENCD-PE-PD-PF (CENCR-PD-F/December 1991) (1105) 1st End  
Mr. Jackson/cld/(312) 886-5471  
SUBJECT: Wyaconda River Basin, Missouri and Iowa

Cdr, North Central Division, U.S. Army Corps of Engineers,  
111 N. Canal Street, Chicago, IL 60606-7205 8 APR 1992

FOR HQUSACE (CECW-P), WASH DC 20314-1000

1. Concur with the district commander's recommendation.
2. The HQ, NCD, POC is Mr. Elihu Jackson, CENCD-PE-PD-PF, (312) 886-5471.

  
RUSSELL L. FUHRMAN  
Brigadier General, USA  
Commanding

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A-1	





DEPARTMENT OF THE ARMY  
NORTH CENTRAL DIVISION, CORPS OF ENGINEERS  
111 NORTH CANAL STREET  
CHICAGO, ILLINOIS 60606-7205  
April 15, 1992

REPLY TO  
ATTENTION OF:

NOTICE OF COMPLETION  
OF  
FINAL RECONNAISSANCE REPORT  
ON  
WYACONDA RIVER BASIN, MISSOURI AND IOWA

This is a notice that the final reconnaissance report on the Wyaconda River Basin, Missouri and Iowa, study has been completed by the District Engineer, Rock Island District, U.S. Army Corps of Engineers, Rock Island, Illinois, and the Division Engineer, North Central Division, U.S. Army Corps of Engineers, Chicago, Illinois.

AUTHORITY

The study was authorized by a resolution of the House Committee on Public Works and Transportation, adopted on September 23, 1987. The purpose of the study was to determine the feasibility of measures for flood control and other water-related purposes in the Wyaconda River Basin, Missouri and Iowa, with particular reference to Clark and Lewis Counties, Missouri.

BACKGROUND

The Wyaconda River Basin is located in Davis and Van Buren Counties, Iowa; and Scotland, Clark, and Lewis Counties, Missouri. The basin is approximately 70 miles in length and 8 miles wide and has a total drainage area of 458 square miles. The basin is predominantly rural and agricultural, except for the four incorporated communities in Missouri: Arbela, Granger, Luray, and Wyaconda.

This study concentrated on the investigation of alternatives to reduce flooding problems along the main stem of the Wyaconda River, downstream of the confluence of the North Wyaconda and South Wyaconda Rivers, in Clark and Lewis Counties, Missouri. The

flooding problems of other portions of the Wyaconda River Basin have either been studied or under consideration for study by the Soil Conservation Service of the U.S. Department of Agriculture.

#### PROBLEMS IDENTIFIED AND ALTERNATIVES CONSIDERED

Flood damages along the main stem of the Wyaconda River, in Clark and Lewis Counties, Missouri, include crop losses, loss of and damage to agriculture land, and damage to roads and bridges.

Alternatives investigated during the study to alleviate the flooding problems included a dam and reservoir, channelization, diversion channel, levees, bridge modifications, permanent floodplain evacuation, and a flood warning system. Each of the structural and nonstructural alternatives investigated was found to be economically infeasible.

#### RECOMMENDATION

The reconnaissance study investigations found none of the flood damage reduction alternatives analyzed for the Wyaconda River Basin, in Clark and Lewis Counties, Missouri, to be economically justified. I, therefore, concur with the recommendation of the district engineer that this study be terminated.

#### REVIEW PROCESS AND ADDITIONAL PUBLIC INPUT

This report is being submitted to the Washington Level Review Center (WLRC) for review and decision making by the Board of Engineers for Rivers and Harbors, Office of the Chief of Engineers, and the Assistant Secretary of the Army for Civil Works.

Interested parties may present written views on the report to the WLRC. We request that information submitted be new, specific in nature, and bear directly on the findings in the report. Previous statements made on the report or views expressed at public meetings are available to the WLRC.

Written communications should be mailed to the Washington Level Review Center, Kingman Building, Fort

Belvoir, Virginia 22060-5576, in time to reach the WLRC by May 15, 1992. If extension of this date is necessary, a written request stating reasons for additional time should be mailed to the WLRC soon after receipt of this notice. Information furnished by mail is given equal consideration and weight as information furnished at public meetings.


Copies of information received by mail will not be furnished to other parties. However, such information will be regarded as public information, unless the correspondent limits its effective value by requesting otherwise. This information may be inspected and notations made by other interested parties in the office of the WLRC.

The Board of Engineers for Rivers and Harbors will not take final action on the report until after expiration of this notice or any extension that may be granted.


#### FURTHER INFORMATION

Further information may be obtained from this office or from the District Engineer; Rock Island District; U.S. Army Corps of Engineers; Clock Tower Building, Post Office Box 2004; Rock Island, Illinois 61204-2004. Additional copies of the report will be available until the limited supply is exhausted. You are requested to give this public notice to anyone known by you who may be interested in the report but did not receive a copy.


Thank you for your continued interest in our activities.

  
Russell L. Fuhrman  
Brigadier General, U.S. Army  
Commanding General and  
Division Engineer

Attachment







REPLY TO  
ATTENTION OF

CENCR-PD-F

DEPARTMENT OF THE ARMY  
ROCK ISLAND DISTRICT, CORPS OF ENGINEERS  
CLOCK TOWER BUILDING - P.O. BOX 2004  
ROCK ISLAND, ILLINOIS 61204-2004

RECONNAISSANCE REPORT  
FLOOD CONTROL AND OTHER WATER-RELATED PURPOSES  
WYACONDA RIVER BASIN, MISSOURI AND IOWA

DECEMBER 1991

REVISED MARCH 1992

## ACKNOWLEDGMENT

This report was prepared by a Rock Island District, U.S. Army Corps of Engineers, multi-disciplinary study team. Individuals familiar with the technical aspects of the study are listed below:

STUDY MANAGEMENT & PLAN FORMULATION	George Gister, AICP
HYDROLOGY AND HYDRAULICS	David Martin, P.E.
ECONOMIC ANALYSIS	Louise Zawlocki
ENVIRONMENTAL RESOURCES	Charlene Carmack
CULTURAL RESOURCES	Ken Barr
COST ESTIMATING	Kent Stenmark
GEOTECHNICAL	Don Bawman
TECHNICAL ASSISTANCE	Diane DeMeyer

## SYLLABUS

This reconnaissance study was authorized by resolution of the Committee on Public Works and Transportation, U.S. House of Representatives, on September 23, 1987. The study was authorized for flood control and other water-related purposes in the Wyaconda River basin, Missouri and Iowa. The Clark County, Missouri, Commission issued letters of support for the study on July 15, 1988; June 22, 1989; and June 4, 1990. A Notice of Initiation for the reconnaissance study was sent to the public on February 5, 1991.

The reconnaissance study investigated a full range of flood damage reduction measures including dams, channelization, diversion channel, levees, and floodplain evacuation.

The study concentrated on the main stem of the Wyaconda River basin downstream of the confluence of the North Wyaconda and South Wyaconda Rivers in Clark and Lewis Counties, Missouri. Other subbasins in the Wyaconda River basin have either been studied or have applications on file with the U.S. Department of Agriculture-Soil Conservation Service under the authority of Public Law 83-566, the Watershed Protection and Flood Prevention Act.

A public open house was held at the Clark County, Missouri, Court House on May 20, 1991. Approximately 55 people attended the open house to comment on the study and to help formulate flood damage reduction plans.

All of the alternatives examined in the report lack economic justification, and, therefore, the study has been terminated.

RECONNAISSANCE REPORT  
FLOOD CONTROL AND OTHER WATER-RELATED PURPOSES  
WYACONDA RIVER BASIN, MISSOURI AND IOWA

TABLE OF CONTENTS

<u>Subject</u>	<u>Page</u>
SECTION 1 - INTRODUCTION	1
Study Authority	1
Study Purpose and Scope	1
Related Studies, Reports, and Existing Water Projects	2
SECTION 2 - PLAN FORMULATION	3
Assessment of Problems and Opportunities	3
Problems and Opportunities	3
Existing Conditions	3
Future Conditions	8
Planning Objectives	8
National Objectives	8
Specific Objectives Within the Study Area	9
Planning Constraints	9
Development of Alternative Plans	9
Available Measures	9
Formulation Criteria	9
Description of Plans	10
Evaluation of Alternative Plans	12
SECTION 3 - SUMMARY OF STUDY MANAGEMENT, COORDINATION, PUBLIC VIEWS & COMMENTS	15
SECTION 4 - RECOMMENDATION	16

List of Tables

<u>No.</u>	<u>Title</u>	<u>Page</u>
1	Bridges on the Wyaconda River Downstream of Confluence of North Wyaconda and South Wyaconda Rivers	11
2	Economic Analysis - 100-Year Level of Protection	14

TABLE OF CONTENTS (Cont'd)

List of Plates

<u>No.</u>	<u>Title</u>
1	Study Area
2	USDA Soil Conservation Service Basin Study Areas
3	Potential Reservoir and Channel Sites
4	Potential Levee Sites I
5	Potential Levee Sites II
6	Potential Levee Sites III
7	Bridges on the Wyaconda River

List of Appendixes

A	Hydrology and Hydraulics
B	Economic Analysis
C	Pertinent Correspondence

DISTRIBUTION LIST

RECONNAISSANCE REPORT  
FLOOD CONTROL AND OTHER WATER-RELATED PURPOSES  
WYACONDA RIVER BASIN, MISSOURI AND IOWA

SECTION 1 - INTRODUCTION

STUDY AUTHORITY

The study was authorized by resolution of the Committee on Public Works and Transportation, U.S. House of Representatives, on September 23, 1987. The resolution is as follows:

Resolved by the Committee on Public Works and Transportation of the United States House of Representatives, that the Board of Engineers for Rivers and Harbors is hereby requested to review the report of the Chief of Engineers on the Wyaconda River, Missouri and Iowa, published as House Document numbered 273, Seventy-fourth Congress, and other pertinent reports, with a view to determining the feasibility of measures for flood control and other water-related purposes in the Wyaconda River basin, Missouri and Iowa, with particular reference to Clark and Lewis Counties, Missouri.

STUDY PURPOSE AND SCOPE

The purpose of the reconnaissance phase is to conduct a study and produce a report to accomplish the following:

- a. Define problems and opportunities and identify potential solutions.
- b. Determine whether the planning should proceed further, into a feasibility phase, based on a preliminary appraisal of consistency with Army policies, cost, benefits, and environmental impacts of the identified potential solutions.
- c. Estimate time and costs for the feasibility phase.
- d. Assess the level of interest and support of non-Federal interests in the identified potential solutions.

This report is the final response to the study authority.

The Wyaconda River basin is located in the northeastern corner of the State of Missouri and the southeastern corner of the State of Iowa. Plate 1 shows the study area.

The study area includes only the main stem of the Wyaconda River basin downstream from the confluence of the North Wyaconda and South Wyaconda Rivers in Clark and Lewis Counties, Missouri. Other subbasins of the Wyaconda River basin have been studied or have applications on file with the U.S. Department of Agriculture-Soil Conservation Service under the authority of Public Law 83-566, the Watershed Protection and Flood Prevention Act (see plate 2).

#### RELATED STUDIES, REPORTS, AND EXISTING WATER PROJECTS

1. *Review of Reports for Flood Control and Allied Purposes on the Wyaconda River, Missouri and Iowa*, U.S. Army Engineer District, Rock Island, Corps of Engineers, Clock Tower Building, Rock Island, Illinois, February 24, 1965. The report investigated flood control and allied purposes in the Wyaconda River basin. All plans for flood control were found to lack economic justification.
2. *Flood Hazard Boundary Map, Clark County, Missouri, Unincorporated Area*, National Flood Insurance Program, Federal Emergency Management Agency, Federal Insurance Administration, Effective Date: September 15, 1981. The maps identify special flood hazard areas.
3. *Flood Hazard Boundary Map, Lewis County, Missouri, Unincorporated Area*, National Flood Insurance Program, Federal Emergency Management Agency, Federal Insurance Administration, Effective Date: September 22, 1981. The maps identify special flood hazard areas.
4. *Little Wyaconda-Sugar Creek Watershed, Watershed Plan-Environmental Assessment, Lewis, Clark, and Scotland Counties, Missouri*, U.S. Department of Agriculture, Soil Conservation Service, Columbia, Missouri, April 1983. The report describes a plan to reduce soil erosion and improve water quality in the Little Wyaconda-Sugar Creek watershed.
5. *Iowa Watershed Progress Report*, U.S. Department of Agriculture, Soil Conservation Service, March 1991. The report references the completed watershed project on the Big Wyacondah (South Wyaconda) and the application awaiting action on the North Wyacondah (North Wyaconda).

## SECTION 2 - PLAN FORMULATION

### ASSESSMENT OF PROBLEMS AND OPPORTUNITIES

#### PROBLEMS AND OPPORTUNITIES

Agricultural lands along the main stem of the Wyaconda River in Clark and Lewis Counties, Missouri, are subject to overbank flooding which causes crop and road damage, erosion, and deposition.

There is an opportunity to reduce crop and road damages due to overbank flooding from the main stem Wyaconda River in Clark and Lewis Counties, Missouri.

#### EXISTING CONDITIONS

##### Hydrology and Hydraulics

The Wyaconda Basin is located in southeastern Iowa and northeastern Missouri. The basin is about 70 miles long, 8 miles wide, and has a drainage area of 458 square miles at the mouth. This study concentrated on the main stem of the Wyaconda River.

The flow frequencies were calculated using the U.S. Geological Survey (USGS) gage at Canton, Missouri, expanded by the USGS gage on the North Fabius River at Monticello, Missouri. The resulting frequencies for the Wyaconda River at Canton are as follows: 10 percent at 12,800 cubic feet per second (cfs), 2 percent at 21,800 cfs, 1 percent at 26,500 cfs, and 0.5 percent at 31,800 cfs.

The water surface profiles were calculated using the Standard Step back-water method of the HEC-2 computer program. The model was set up using surveyed bridge openings and USGS 20-foot contour maps to develop cross sections and reach lengths.

Additional information can be found in Appendix A-Hydrology and Hydraulics.



## Economic and Social

The Wyaconda River Basin is located within Davis and Van Buren Counties, Iowa, and Scotland, Clark, and Lewis Counties, Missouri. The study area encompasses the Wyaconda River main stem in Clark and Lewis Counties.

Four incorporated communities are within the Wyaconda River basin, all within Missouri: Arbela, Granger, Luray, and Wyaconda. Land use in the study area is in agricultural production.

Transportation service for the study area is from State Highway 81 along the east side, State Highway 16 to the south, numerous county highways to the west, and U.S. Route 136 to the north.

The study area is subject to flood-induced agricultural, transportation, and road damages. The estimated average annual damages for existing condition crop losses in the study area are \$1,477,000.

Scattered throughout the study area are numerous privately constructed levees which provide varying degrees of protection to the area. These levees provide no systematic flood control system. Additional information is provided in Appendix B-Economic Analysis.

## Geology and Soils

Topography - The Wyaconda River system has incised itself into the geomorphic province known as the Dissected Glacial Till Plain. This province is composed of Kansan age, or possibly older, glacial till overlain by a mantle of loess. It is generally characterized by a relatively flat, loess-covered upland, moderately steep valley walls, and moderately broad valley floors. This is essentially the nature of the Wyaconda drainage basin. The basin is extremely narrow and generally straight from its head near Bloomfield, Iowa, to its mouth near La Grange, Missouri. The upper three-quarters of the basin has flat, loess-covered uplands between valleys, with till walls of a slope seldom greater than 20 percent and generally less than 14 percent. The normal elevation change from upland to valley floor is a relatively constant 100 to 120 feet. Originally, the streams meandered along flat valley floors of loess and till alluvium. Recently, however, many stretches have been dredged and straightened. In the lower reach of the basin, the valleys narrow, the valley walls steepen, and the river retains its original sinuosity. From the vicinity of Canton, the river impinges against very steep bluffs or rock cliffs until it debouches onto the Mississippi River valley floor near La Grange.

Surficial Geology - The unconsolidated surface deposits range from zero to 400 feet thick, but generally vary from 25 to 250 feet. The uppermost unit is the wind-blown loess which is silt-size material that was blown from the glacial sluiceways onto the adjacent till plains. It generally ranges from

5 to 10 feet in thickness, but locally may approach 50 feet. Beneath this is Kansan age glacial till composed of a heterogeneous mix of boulders, gravels, sands, silts, and clays. The upper zone of the till is a developed paleosol which grades downward into the unleached till. Thickness in the till ranges from 20 to 200 feet. Underlying some areas of till are pre-Kansan alluvial deposits of channel sands and gravels. Modern streams have cut down through the loess and till to form typical alluvial valley deposits which are generally less than 50 feet thick.

Bedrock Geology - The basin area is underlain by Paleozoic sedimentary rocks. From the headwaters to approximately the Scotland-Clark County, Missouri, border, the bedrock surface is represented by the Pennsylvanian age Cherokee Group, composed of predominantly sandstones, siltstones, and shales, with interspersed limestones and coals, varying up to 250 feet thick. The underlying and older Mississippian Merimecian Series comprises the bedrock surface from roughly the Scotland-Clark County border to the vicinity of Canton, Missouri, where the Osagean Series is expressed to the vicinity of La Grange. The Mississippian rocks are predominantly carbonates with abundant chert and occasional shale beds from 200 to 450 feet thick. Below this are roughly 1,000 feet of Devonian and Ordovician carbonates with interbedded shales and sandstones. The Cambrian strata are predominantly sandstones with shales and carbonates, all of which rest on the Precambrian basement.

Hydro-Geology - Surficial aquifers are of three types. Alluvial aquifers exist in the shallow, modern valley sediments of silts, sands, and gravels and produce moderate to large yields (25 to 100 gpm). The glacial drift contains occasional irregular bodies of sand and gravel which can produce locally but are generally low (less than 10 gpm). Pre-drift buried channel deposits of sands and gravels are relatively extensive and can produce large yields. The Pennsylvanian rocks, where present, function as an aquiclude overlying the Mississippian aquifer which gives moderate to low yields. Below this is an alternating succession of aquicludes and aquifers of varying yields down to the Precambrian which is the base of the ground water reservoir.

#### Historic Properties

Few systematic archeological surveys have been conducted for the Wyaconda River basin. The minimal data available suggest that cultural developments seem to parallel those of the better known Salt River basin to the south.

Sites dating from the Archaic through Mississippian periods are anticipated.<sup>1</sup>

Each alternative considered has a potential to impact significant historic properties, and detailed inventory and evaluation studies would be required as part of any future Federal flood control study for the project area. Impacts to both historic structures (bridges, buildings) and archeological sites would need to be assessed for compliance with the National Historic Preservation Act.

### Biological

The study area is primarily agricultural in character. The Wyaconda River is the principal aquatic resource in the area. The river flows in a generally southeasterly direction from its headwaters in Davis County, Iowa; through Scotland, Clark, and Lewis Counties in Missouri; and empties into the Mississippi River at the town of La Grange, Missouri. The majority of the basin's acreage is in row crop production.

Following initiation of the reconnaissance study, various Federal and State resource agencies were requested to provide input or comments concerning existing environmental conditions, problems, and opportunities in the study area. The U.S. Fish and Wildlife Service (USFWS), the U.S. Environmental Protection Agency, the Missouri Department of Conservation, the Missouri Department of Natural Resources, and the U.S. Department of Agriculture-Soil Conservation Service, provided information and assistance for the assessment of biological resources in the study area. Copies of coordination letters from these agencies are contained in Appendix C-Pertinent Correspondence.

The Planning Assistance Letter provided by the USFWS to the Rock Island District reported that aquatic habitat in the Wyaconda River basin has been severely reduced and constrained by historic and contemporary alteration of natural drainage patterns and vegetative cover. The upper part of the main stem of the Wyaconda, the primary focus of this study, has been extensively channelized, as have the headwaters of the river and its tributaries. The USFWS estimates that the river has lost approximately 50 percent of its length with a corresponding decrease in aquatic habitat.

---

<sup>1</sup> Wright, Christopher A., 1987, Part B: Study Units in *Master Plan for Archeological Resource Protection in Missouri*, D. Weston and M. Weichman (editors).

Cultivation activities also have increased the rate of erosion, sedimentation, and organic inputs, further contributing to deterioration of aquatic habitat. Despite these limiting factors, the river and its tributaries support a viable warm-water fishery. At least 52 fish species are known to occur in the Wyaconda River system. Common species are listed in the Planning Assistance Letter.

Terrestrial habitat in the study area also has been significantly affected by agricultural activities. Pre-settlement prairie vegetation has been virtually eradicated, and upland forest habitat has been reduced by grazing and timber harvesting. The largest amount of remaining natural vegetation exists in fragmented tracts of bottomland forest located along the current and historic channels of the Wyaconda River and its tributaries. Wildlife species which inhabit the area are primarily species which utilize more than one habitat type and are commonly found in agricultural-edge environments. A partial listing of avian and mammal species found in the study area is provided in the Planning Assistance Letter.

Examination of the USFWS's National Wetlands Inventory maps revealed that wetland resources in the study area are primarily palustrine forested, shrub-scrub or emergent wetlands associated with the floodplain of the Wyaconda River. Wetland resources in the uplands adjacent to the study area are primarily associated with farm ponds (unconsolidated bottom wetlands). The Planning Assistance Letter states that the Soil Conservation Service's wetlands inventory findings are similar to those of the USFWS inventory, and that the Soil Conservation Service inventory additionally identified a large number of farmed wetlands in the floodplain of the Wyaconda.

The USFWS has determined that the following federally listed endangered or threatened species may occur in the study area: the bald eagle (*Haliaeetus leucocephalus*), the fat pocketbook pearly mussel (*Potamilus capax*), the Higgins' eye pearly mussel (*Lampsilis higginsii*), and the Indiana bat (*Myotis sodalis*). No designated critical habitat for any of these species occurs in the study area. The Missouri Department of Conservation reported that another federally listed species, the winged mapleleaf mussel (*Quadrula fragosa*), may potentially occur in the study area; however, the USFWS report contained no reference to this species. The Department of Conservation also reported that the following State-listed endangered species may occur in the study area: Blanding's turtle (*Emydoidea blandingii*), the western fox snake (*Elaphe vulpina vulpina*), the eastern massasauga (*Sistrurus catenatus catenatus*), the central mudminnow (*Umbra limi*), and the dotted monarda (*Monarda punctata*).

Coordination with the U.S. Environmental Protection Agency disclosed that their CERCLIS (abandoned, inactive, or uncontrolled hazardous waste sites) data base contained no records of CERCLIS sites within the study area, although there are several recorded sites in the headwaters of the basin in Iowa and one in the city of La Grange, Missouri. The lack of recorded sites in the study area does not necessarily preclude the existence of

presently unknown CERCLIS sites, but it is perhaps indicative of the essentially rural nature of this area.

The downstream portion of the Wyaconda River below the reconnaissance study area has been recognized by the Department of Natural Resources for its scenic and recreational value, and by the Department of Conservation's Natural Areas Inventory as a "significant area" because of numerous undisturbed upland plant communities located on the bluff line and adjacent ravines.

Should more detailed flood control studies be undertaken at some future date, more extensive analysis and coordination of potential impacts to environmental resources will be required. For studies culminating in a recommendation for project construction or other Federal action, a NEPA document will be required. Resource agencies which provided comments and input regarding the alternatives investigated during this study generally recommended against structural solutions that would increase the physical alteration of the original river channel and floodplain.

#### FUTURE CONDITIONS

Because of the existing flooding problems, farmers incur increasing expenses and crop losses. A continually rising expense is to adequately maintain roads and drainage ditches because of the flooding problem. If no action is taken, flooding will continue to inundate the study area, and the resultant expenses and losses will diminish economic resources.

#### PLANNING OBJECTIVES

##### NATIONAL OBJECTIVES

The Federal objective of water and related land resources planning is to contribute to national economic development consistent with protecting the Nation's environment, pursuant to national environmental statutes, applicable executive orders, and other Federal planning requirements.

Contributions to national economic development (NED) are increases in the net value of the national output of goods and services, expressed in monetary units. Contributions to NED are the direct net benefits that accrue in the planning area and the rest of the Nation. Contributions to NED include increases in the net value of those goods and services that are marketed, and also of those that may not be marketed.

## SPECIFIC OBJECTIVES WITHIN THE STUDY AREA

It is a specific objective in the study area to reduce damages from over-bank flooding on the main stem of the Wyaconda River in Clark and Lewis Counties, Missouri.

## PLANNING CONSTRAINTS

A number of planning constraints must be considered in the formulation of project alternatives. In general, the study is constrained by all applicable laws of the United States and the States of Iowa and Missouri, all Executive Orders of the President, the Water Resources Council's Principles and Guidelines, and all regulations of the Corps of Engineers.

## DEVELOPMENT OF ALTERNATIVE PLANS

### AVAILABLE MEASURES

The range of available measures can be divided into two categories: structural and nonstructural. Structural measures include dams with reservoirs/dry dams, channelization, diversion channel, levees and floodwalls, and bridge modifications. All such measures reduce the frequency or extent of damaging flows.

Nonstructural measures include permanent floodplain evacuation and a flood-warning system. These may be used alone or in conjunction with structural measures.

### FORMULATION CRITERIA

Plans are formulated in consideration of four criteria:

- a. Completeness is the extent to which a given alternative plan provides and accounts for all necessary investments or other actions to ensure the realization of the planned effects. This may require relating the plan to other types of public or private plans if the other plans are crucial to realization of the contributions to the objective.
- b. Effectiveness is the extent to which an alternative plan alleviates the specified problems and achieves the specified opportunities.
- c. Efficiency is the extent to which an alternative plan is the most cost effective means of alleviating the specified problems and realizing

the specified opportunities, consistent with protecting the Nation's environment.

d. Acceptability is the workability and viability of the alternative plan with respect to acceptance by State and local entities and the public and compatibility with existing laws, regulations, and public policies.

A plan that reasonably maximizes net economic development benefits, consistent with the Federal objective, is to be formulated. This plan is to be identified as the national economic development plan.

## DESCRIPTION OF PLANS

Seven alternatives were formulated for the study area:

### Dam with Reservoir/Dry Dam

A reservoir is a man made lake used to temporarily store excess runoff. These structures are constructed upstream of areas that encounter significant flooding problems. In order to protect the study area, reservoirs would have to be placed on both the North and South Wyaconda Rivers. The North Wyaconda reservoir would require about 3 square miles, and the South Wyaconda reservoir would require about 3-1/2 square miles (see plate 3).

### Channelization

Channelization improves a stream's conveyance of water by realignment, widening, or deepening of the streambed. Channel modifications of as much as 48 miles in length would be required for this alternative.

There are two alternatives for the construction of a channel. The long channel would start near the confluence of the North Wyaconda and South Wyaconda Rivers and extend as far as the confluence with the Mississippi River. The short channel would start near the confluence of the North Wyaconda and South Wyaconda Rivers and extend as far as the area of the Clark/Lewis county line (see plate 3).

### Diversion Channel

A diversion channel would be constructed in the vicinity of Canton, Missouri, to divert the Wyaconda River to the Mississippi River. The diversion channel would be about 8,000 feet in length (see plate 3).

### Levees and Floodwalls

A system of 12 levees was formulated for the broad floodplain area extending from the confluence of the North Wyaconda and South Wyaconda Rivers downstream to the area of the Clark/Lewis county line (see plates 4 to 6). There would be six levees on the left descending bank (Left 1 thru 6) and six levees on the right descending bank (Right 1 thru 6). Levees would be constructed of compacted earthen fill with 3 horizontal to 1 vertical side slopes and a 10-foot top. Existing roads would be ramped over the levee. Measures would be included for pumping or ponding interior drainage. Levee alternatives were formulated for the 10-, 100-, and 500-year levels of protection.

### Bridge Modifications

Modifications to bridges are performed when the bridges impede stream flow. By modifying or removing the bridge, flood profiles can be lowered, which may reduce flooding in affected areas.

There are 15 bridges on the Wyaconda River downstream from the confluence of the North and South Wyaconda Rivers. Bridges are listed in table 1 and located on plate 7.

TABLE 1

*Bridges on the Wyaconda River  
Downstream of Confluence of  
North Wyaconda and South Wyaconda Rivers*

<u>Bridge</u>	<u>Approximate Distance Above Mouth (Miles)</u>
Burlington Northern RR	0.1
State Highway B	0.2
U.S. Highway 61	6.6
State Highway V	8.3
State Highway C	13.3
State Highway 16	16.7
County Road	20.3
State Highway E	26.9
County Bridge 367	33.1
County Bridge 358	35.0
County Bridge 264	37.7
County Bridge 257	39.0
State Road D	41.5
County Bridge 238	43.9
A, T&SF Railroad	48.1



### Permanent Floodplain Evacuation

Permanent floodplain evacuation involves acquiring affected homes or businesses and relocating the occupants and their possessions to homes or buildings that are outside of the floodplain, of similar worth, and in decent, safe, and sanitary condition. Relocation of homes or businesses involves physically lifting the structure off its present foundation, moving it, and then lowering it onto a suitable foundation outside of the floodplain. Relocation is considered where it is structurally feasible and less costly than evacuation. Some structures, e.g., those constructed of brick or steel, are not normally relocated due to structural limitations.

The area is primarily agricultural, and permanent floodplain evacuation would involve purchasing affected areas and converting land uses to non-agricultural practices. This could include recreation or fish and wildlife purposes. A non-Federal governmental unit would be responsible for managing these areas.

### Flood-Warning System

A flood-warning system is a water level sensing device or devices which are connected to an alarm. As water levels rise and reach a potentially threatening level, the alarm is activated. This would alert county officials of imminent flooding and prompt them to warn affected residents via some public address system. Flood-warning systems help to assure residents' safety by providing evacuation time.

### EVALUATION OF ALTERNATIVE PLANS

Four accounts are established to facilitate evaluation and display of the effects of alternative plans. These accounts are: national economic development (NED), environmental quality (EQ), regional economic development (RED), and other social effects (OSE). These four accounts encompass all significant effects of the plan on the human environment and encompass social well-being.

The national economic development account shows effects on the national economy. The environmental quality account shows effects on ecological, cultural, and aesthetic attributes of significant natural and cultural resources that cannot be measured in monetary terms. The regional economic development account shows the regional incidence of national economic development effects, income transfers, and employment effects. The other social effects account shows urban and community impacts and effects on life, health, and safety.

An initial evaluation of the slate of alternatives was conducted to identify the options with the greatest likelihood of justification. The evaluation was based upon experience with similar projects, expected benefits and costs, and professional judgment. The following alternatives were eliminated from further consideration as noted.

Dam with Reservoir/Dry Dam - The relatively high cost of constructing a dam would not justify the relatively low value of bridge and crop damages due to flooding. The expected benefit-to-cost ratio would be less than 0.10.

Channelization - The relatively high cost and adverse environmental impacts of constructing a channel would not justify the relatively low value of bridge and crop damages due to flooding. The expected benefit-to-cost ratio would be less than 0.10.

Diversion Channel - The cost of a diversion channel would far exceed the possible level of benefits for the prevention of crop and bridge damages. The diversion channel alternative would cost over \$20 million and have a benefit-to-cost ratio less than 0.20.

Flood-Warning System - A flood-warning system would not be practical for the study area since most damages are sustained by crops and bridges.

Floodwalls - Floodwalls can be replaced by less costly earthen levees in the study area.

Bridge Modifications - Damages caused by flooding of bridges and flooding of upstream properties due to higher water surface profiles caused by constrictions are not sufficiently great to justify modifications to existing structures. Bridges in the study area subject to the greatest flood threat have low traffic counts.

Permanent Floodplain Evacuation - The study area floodplain is essentially clear of any structures and there are no opportunities for permanent floodplain evacuation.

A detailed evaluation was made of the levee alternatives for each of 12 reaches as shown on plates 4, 5, and 6. Estimated average annual damages and benefits for a 10-, 100-, and 500-year level of protection were determined and benefit-to-cost ratios computed. Appendix B-Economic Analysis gives this analysis. Table 2 shows the project first costs, average annual costs and benefits, and benefit-to-cost ratios for levees providing protection to the 100-year flooding event. The economic analyses for the 10- and 500-year flooding events had similar benefit-to-cost ratios. "L" refers to the left descending bank of the Wyaconda River and "R" refers to the right descending bank.

TABLE 2

*Economic Analysis - 100-Year Level of Protection*  
*(in \$1,000's)*

<u>Reach</u>	<u>Project First Costs</u>	<u>Average Annual Cost</u>	<u>Average Annual Benefit</u>	<u>Net Benefit</u>	<u>Benefit- to-Cost Ratio</u>
L-1	\$ 2,586	\$ 230	\$ 28	\$ (202)	0.12
L-2	2,399	214	36	(178)	0.17
L-3	3,347	298	25	(273)	0.08
L-4	2,503	223	51	(172)	0.23
L-5	2,107	188	31	(157)	0.17
L-6	4,276	380	82	(298)	0.22
R-1	2,711	242	4	(238)	0.02
R-2	2,795	249	41	(208)	0.16
R-3	2,649	236	11	(225)	0.05
R-4	12,517	1,114	100	(1,014)	0.09
R-5	7,216	642	69	(573)	0.11
R-6	5,819	518	178	(340)	0.34

### SECTION 3 - SUMMARY OF STUDY MANAGEMENT, COORDINATION, PUBLIC VIEWS & COMMENTS

The Rock Island District, U.S. Army Corps of Engineers, announced the start of the Wyaconda River Basin Study on February 5, 1991, in its *Notice of Initiation of a Reconnaissance Study for Flood Control and Other Water-Related Purposes for the Wyaconda River Basin, Missouri and Iowa*. This notice was mailed to those on the Wyaconda River basin distribution list, which included approximately 200 Federal, State, county, and city governmental agencies and representatives, local media, and residents within the Wyaconda River basin study area. A copy of the Notice of Initiation is included in Appendix C-Pertinent Correspondence.

On May 5, 1991, an invitation to attend an open house was mailed to the Wyaconda River Basin distribution list. The open house was held at the Court House in Kahoka, Missouri, on May 20, 1991. The open house notice is included in Appendix C-Pertinent Correspondence.


Approximately 55 people attended the open house, including local Soil Conservation Service representatives, Clark County commissioners, Wyaconda Basin area farmers and residents, and five Corps of Engineers study team members. The attendees were asked either to fill out a comment sheet at the open house or to take the sheet with them for completion and then mail it to the Corps' Rock Island District office. Attendees were encouraged to take comment sheets to those who could not attend the open house. The comment sheets were used to update the Wyaconda River basin distribution list and to help the study team formulate its study alternatives.

The main problems listed on the comment sheets, listed here in order of number of times mentioned, were flood damage, loss of and damage to crop and pasture land, erosion, damage to roads and bridges, and damage to fences. Among the other concerns were the sharp bends of the Wyaconda River, water quality, and the effects of flooding on livestock and wildlife.



A *Notice of Study Progress* was mailed to the Wyaconda distribution list on July 17, 1991, that discussed study progress, the open house results, and the remainder of the work involved in the reconnaissance study phase. A copy of the notice is included in Appendix C-Pertinent Correspondence.

#### SECTION 4 - RECOMMENDATION


I recommend that the study conducted to determine the feasibility of measures for flood control and other water-related purposes in the Wyaconda River basin, Missouri, with particular reference to Clark and Lewis Counties, Missouri, be terminated. The study lacks economic justification for a broad range of alternatives. Some Wyaconda River subbasins' water resource needs may be best addressed by the U.S. Department of Agriculture-Soil Conservation Service under the authority of Public Law 83-566, the Watershed Protection and Flood Prevention Act.

  
John R. Brown  
Colonel, U.S. Army  
District Engineer


REVISED MARCH 1992



State of Missouri  
PROJECT LOCATION




LEGEND:


 CORPS OF ENGINEERS  
STUDY AREA


2 0 5  
SCALE IN MILES


GENERAL INVESTIGATION  
Wyaconda River  
Basin  
IOWA AND MISSOURI  
FLOOD DAMAGE  
REDUCTION STUDY  
  
STUDY AREA


















VICINITY MAP

50 0 100  
SCALE IN MILES




PLATE INDEX

KEY:

- ▲▲▲▲ PROPOSED LEVEE
- SECONDARY ROAD

2000' 0 3000'  
SCALE IN FEET

GENERAL INVESTIGATION

Wyaconda River Basin

IOWA AND MISSOURI

FLOOD DAMAGE  
REDUCTION STUDY

POTENTIAL LEVEE SITES I

MATCH LINE - PLATE 4


R3 Levee



L3 Levee

L4 Levee

R4 Levee

LITTLE WYACONDA RIVER





VICINITY MAP

50 0 100  
SCALE IN MILES




PLATE INDEX

KEY:

- ▲▲▲▲ PROPOSED LEVEE
- SECONDARY ROAD

2000' 0 3000'  
SCALE IN FEET

GENERAL INVESTIGATION

Wyaconda River Basin

IOWA AND MISSOURI

FLOOD DAMAGE  
REDUCTION STUDY

POTENTIAL LEVEE SITES II

U.S. Army Corps of Engineers  
Rock Island District November 19

PLATE

MATCH LINE - PLATE



R5 Levee

CLARK COUNTY  
LEWIS COUNTY

R6 L







VICINITY MAP  
 50 0 100  
 SCALE IN MILES






PLATE INDEX

KEY:  
 ▲▲▲▲ PROPOSED LEVEE  
 ——— SECONDARY ROAD  
 2000' 0  
 SCALE IN FEET


GENERAL INVESTIGATION  
 Wyacunda River Basin  
 IOWA AND MISSOURI  
 FLOOD DAMAGE  
 REDUCTION STUDY  
 POTENTIAL LEVEE SYSTEM  
 U.S. Army Corps of Engineers  
 Rock Island District

I C W



State of Missouri  
PROJECT LOCATION

State High



HYDROLOGY AND HYDRAULICS

A

P

P

E

N

D

I

X

A

RECONNAISSANCE REPORT  
FLOOD CONTROL AND OTHER WATER-RELATED PURPOSES  
WYACONDA RIVER BASIN, MISSOURI AND IOWA

APPENDIX A  
HYDROLOGY & HYDRAULICS

TABLE OF CONTENTS

<u>Subject</u>	<u>Page</u>
General	
Site Location	A-1
Climatology	A-1
Wyaconda Basin	A-1
General	A-2
Flood Frequency	A-2
Water Surface Profiles	A-2
	A-3
References	
	A-4

List of Tables

<u>No.</u>	<u>Title</u>	<u>Page</u>
A-1	Climate	
A-2	Wyaconda River at Canton, Missouri, Flow Frequency	A-1
		A-2

List of Plates

<u>No.</u>	<u>Title</u>
A-1	Flow Frequency Analysis
A-2	
thru	Flood Profiles, Wyaconda River
A-9	

RECONNAISSANCE REPORT  
FLOOD CONTROL AND OTHER WATER-RELATED PURPOSES  
WYACONDA RIVER BASIN, MISSOURI AND IOWA

APPENDIX A  
HYDROLOGY & HYDRAULICS

GENERAL

**SITE LOCATION**

The Wyaconda River basin is located in southeastern Iowa and north-eastern Missouri. The North and South Wyaconda Rivers begin just south of Bloomfield, Iowa, and run southeast through Davis County, Iowa, and Scotland County, Missouri, before converging to form the Wyaconda River in Clark County, Missouri. From there, the river flows through Lewis County where it enters the Mississippi River near La Grange, Missouri. The Wyaconda basin has a drainage area of 458 square miles. Plate 1 in the main report shows the project location.

**CLIMATOLOGY**

The climate of the area is typically continental with changeable weather and a wide range of temperature extremes. Table A-1 summarizes the climate of four stations in the immediate vicinity of the Wyaconda basin: Bloomfield, Iowa, just to the north; Memphis, Missouri, to the west; Kahoka, Missouri, to the east; and Canton, Missouri, near the mouth.

TABLE A-1

*Climate*

<u>Location</u>	<u>Average Snowfall (inches)</u>	<u>Average Precip (inches)</u>	<u>Max Avg High Temp (deg F/month)</u>	<u>Min Avg Low Temp (deg F/month)</u>
Bloomfield	27.25	35.61	88 in Jul	13 in Jan
Memphis	25.07	34.35	89 in Jul	13 in Jan
Kahoka	24.51	37.44	88 in Jul	13 in Jan
Canton	22.93	36.39	88 in Jul	16 in Jan

## WYACONDA BASIN

### GENERAL

The Wyaconda basin is about 70 miles long and 8 miles wide, with a narrow floodplain bordered by rolling hills which become rolling prairies to form the divide with the adjacent watersheds. The tributary streams tend to be short and flow into the Wyaconda and its two main tributaries perpendicular to the channel. Approximately 67 miles of the Wyaconda and its north and south branches were straightened in the 1920's. The river is now showing some signs of reverting to its old meanders. The area is predominantly agricultural, featuring corn, soybeans, and pasture. Population is sparse. There are no occupied buildings within the floodplain.

### FLOOD FREQUENCY

The Wyaconda River has a U.S. Geological Survey (USGS) gage at Canton, Missouri (49600) with a continuous record from 1923 through 1988, except for 4 years in the mid-1970's (1973, 1974, 1975, and 1977), that was used in this study. The record at Canton was compared to and lengthened by the North Fabius River at Monticello, Missouri (49700) because 1973 had a record flow in this adjacent watershed. The resulting correlation was 93 percent, with an equivalent period of record of 66.5 years. Flow frequencies were calculated using Bulletin 17B (Reference A) methodology. The resulting flow frequency relationship was confirmed by the Missouri regression equations and an HEC-1 model. The flow frequency for Canton is shown in table A-2 and on plate A-1. This frequency curve was moved to key locations on the Wyaconda by means of the ratio of the square root of the drainage area.

TABLE A-2

*Wyaconda River at Canton, Missouri*  
*Flow Frequency*

<u>Exceedence Frequency</u> <u>(Percent)</u>	<u>Flow</u> <u>(cfs)</u>
0.2	39,900
0.5	31,800
1.0	26,500
2.0	21,800
5.0	16,300
10.0	12,800
20.0	9,540

## WATER SURFACE PROFILES

The hydraulic analysis for the study was conducted using the U.S Army Corps of Engineers HEC-2 Water Surface Profiles computer program (Reference B). The program uses the backwater computational procedure generally known as the Standard Step Method to calculate the water surface profiles. The profiles were calculated from the mouth of the Wyaconda to the confluence of the North and South Wyaconda Rivers. The analysis for this project used surveyed bridge openings and USGS 20-foot contour maps to develop cross sections and reach lengths. The channel roughness factors (Manning's "n") used in the hydraulic computation were chosen by engineering judgment based on field observations. For the Wyaconda River channel, the "n" values ranged from 0.035 to 0.04, and for the overbank area they ranged from 0.04 to 0.095, reflecting the changes from smooth grass and barren soil to heavily wooded areas. Profiles from historic flows compared favorably to the Canton gage readings. Computational flows compared favorably to the rating curve and design water surface elevations shown on bridge designs.


The water surface profiles for the 10-, 5-, 2-, 1-, 0.5-, and 0.2-percent floods are shown on plates A-2 through A-9. These profiles show pre-project conditions.



## REFERENCES


A. Bulletin 17B; Guidelines for Determining Flood Flow Frequency; Interagency Advisory Committee on Water Data; U.S. Geological Survey, September 1981.

B. HEC-2 Water Surface Profiles, U.S. Army Corps of Engineers, Hydraulic Engineering Center, May 1984.



# FLOOD PROFILES


Wyconda River



Burlington Northern  
State Hwy. B


# FLOOD PROFILES

Wyaconda River




# FLOOD PROFILES

Wyaconda River




# FLOOD PROFILES

Wyconda River




# FLOOD PROFILES

Wyaconda River



# FLOOD PROFILES


Wyconda River






# FLOOD PROFILES

Wyandona River



# FLOOD PROFILES

Wyaconda River



ECONOMIC ANALYSIS

A

P

P

E

N

D

I

X

B

RECONNAISSANCE REPORT  
FLOOD CONTROL AND OTHER WATER-RELATED PURPOSES  
WYACONDA RIVER BASIN, MISSOURI AND IOWA

APPENDIX B  
ECONOMIC ANALYSIS

TABLE OF CONTENTS

<u>Subject</u>	<u>Page</u>
Study Area Characteristics	B-1
General	B-1
Study Area	B-1
Socio-Economic Conditions	B-1
Historic Flooding	B-3
Existing Conditions	B-3
Flood Damages	B-3
Methodology	B-3
Agricultural Damages	B-4
Transportation Damages	B-4
Road Repairs	B-8
Alternatives	B-9
Average Annual Damages and Benefits	B-9
Location Benefits	B-9
Intensification Benefits	B-9
Redevelopment Benefits	B-9
Diversion Channel	B-10
Average Annual Costs	B-10
Economic Summary	B-12
Levees	B-12
Sensitivity Analysis	B-13

List of Tables

<u>No.</u>	<u>Title</u>	<u>Page</u>
B-1	Population Trends	B-2
B-2	Labor Force Data	B-2
B-3	Average Dollar Damage Value Per Acre-Corn	B-5
B-4	Bridges in the Study Area	B-6
B-5	Annual Number of Trips	B-6
B-6	Vehicle Operating Costs for a 1-Year Detour	B-7
B-7	Opportunity Time Costs for a 1-Year Detour	B-8
B-8	Average Annual Damages and Benefits-Diversion Channel	B-10
B-9	Interest During Construction-Diversion Channel	B-11
B-10	Average Annual Costs-Diversion Channel	B-11

TABLE OF CONTENTS (Cont'd)

List of Tables (Cont'd)

<u>No.</u>	<u>Title</u>	<u>Page</u>
B-11	Economic Analysis Summary-Diversion Channel	
B-12	Average Annual Damages and Benefits-Levees	B-12
B-13	Interest During Construction	B-13
B-14	Average Annual Costs	B-14
B-15	Economic Analysis Summary	B-16
		B-18

RECONNAISSANCE REPORT  
FLOOD CONTROL AND OTHER WATER-RELATED PURPOSES  
WYACONDA RIVER BASIN, MISSOURI AND IOWA

APPENDIX B  
ECONOMIC ANALYSIS

STUDY AREA CHARACTERISTICS

**GENERAL**

The Wyaconda River basin is located within Davis and Van Buren Counties, Iowa, and Scotland, Clark, and Lewis Counties, Missouri. The basin covers a 458-square-mile area, is about 70 miles long, and is 8 miles wide at its widest point. The river headwaters are in Davis County, near Bloomfield, Iowa. The Wyaconda River flows southeasterly to the Mississippi River near La Grange, Missouri.

**STUDY AREA**

The study area begins directly after the confluence of the North and South Wyaconda Rivers into the Wyaconda River. The U.S. Department of Agriculture-Soil Conservation Service is and will be working on several projects located along the North and South Wyaconda Rivers and various creeks in the Wyaconda River basin under Public Law 83-566, the Watershed Protection and Flood Prevention Act.

**SOCIO-ECONOMIC CONDITIONS**

Four incorporated communities are within the Wyaconda River basin, all within Missouri: Arbela, Granger, Luray, and Wyaconda.

Communities located within less than 10 miles from the study project area include Memphis, Prospect Grove, Azen, Brock, Gorin, Ashton, Kahoka, Fairmont, Neeper, Antioch, St. Patrick, Williamstown, Benjamin, Monticello, Canton, and La Grange, Missouri. The nearest industrial centers in Iowa are Ottumwa (1985 pop. 27,381), approximately 20 miles north of Bloomfield; and Keokuk (1985 pop. 13,536), approximately 30 miles from the center of the basin. Hannibal, Missouri (1985 pop. 22,722), located approximately 20 miles west of the southern tip of the basin, is the nearest Missouri industrial center.

U.S. Highway 136, an east-west highway, traverses the northern portion of the basin. East-west Missouri Highway 16 traverses the southern tip of the basin. Missouri Highway 15, a north-south highway, traverses the northern portion of the basin. The Atchison, Topeka, and Santa Fe Railway crosses the Wyaconda and Little Wyaconda Rivers in Clark County, Missouri.

Table B-1 shows the comparative historic population for the four communities within the basin. County populations shown reflect an approximation of residents within the basin based upon the percentage of basin within the study area.

TABLE B-1

*Population Trends*

	<u>Pop.</u> <u>1960</u>	<u>Pop.</u> <u>1970</u>	<u>Pop.</u> <u>1980</u>	<u>Pop.</u> <u>1990</u>
Arbela	70	70	67	40
Granger	146	105	91	63
Luray	154	149	175	70
Wyaconda	402	356	359	347
Clark County	2,685	2,561	2,633	2,317
Lewis County	4,068	4,015	4,038	3,790

Source: United States Bureau of the Census.

Table B-2 presents the labor force data for the various communities within the study area. Employment is concentrated in agriculture, manufacturing, and professional and related services.

TABLE B-2

*Labor Force Data*

	<u>Percent</u> <u>Distribution</u>
Agriculture	32.2
Manufacturing	21.3
Professional and Related Services	17.6
Wholesale and Retail Trade	14.2
Construction and Transportation	10.5
Finance, Insurance, and Real Estate	2.4
All Other	1.8

Source: Claritis Corporation, *REZIDE 1985*, The National Encyclopedia of Residential ZIP Code Demography.

## HISTORIC FLOODING

Historic flooding in the study area is detailed in the Appendix A-Hydrology and Hydraulics. The study area in Clark County was severely inundated by the 1986 flood, which was a 25-year frequency event. The basin valley is flat, and storms with a 2-year frequency can inundate farmlands, bridges, and roads in the basin. The September 1986 flood was the most recent major flood of record.

## EXISTING CONDITIONS

There were no flooding problems in communities within or adjoining the study area. Overbank flooding inundates agricultural lands and causes crop and road damage, soil erosion, and silt deposition.

Numerous private agricultural levees, of varying design height, are located throughout the Wyaconda River floodplain, but no formalized flood control system exists. Most of the September 1986 flood damages were concentrated in the Clark County, Missouri, portion of the basin. The majority of the lands affected are in agricultural production. Floods generally occur during the crop-growing season, and ponding is of sufficient duration to destroy all affected crops. Because of the flooding duration, it is not possible or economically practical to attempt replanting.

## FLOOD DAMAGES

## METHODOLOGY

The economic analysis was performed in accordance with Public Law 89-80, Guidelines Sections III and IV.

The study area is defined as that area immediately or directly affected by the project. For purposes of analysis, the study area was separated into 12 separate reaches, 6 on each side of the Wyaconda River main stem (see plate 1 in the main report). An inventory of the study area was made in March 1991. The survey indicated there are no residential structures within the floodplain.

In computing flood damages, no credit was given to existing privately constructed levees. The plans examined for this study phase involved providing protection to the entire study area by constructing a diversion channel. Also analyzed were construction of individual levees for each of the 12 separate reaches to provide protection from the 10-, 100-, and 500-year flooding events.



## **AGRICULTURAL DAMAGES**

An estimated 9,200 acres of cropped land are susceptible to inundation in the study area. Estimated cropping distribution is split between corn and soybeans. Damage per acre for the growing season was calculated by averaging the minimum and maximum potential damage which could occur during the growing season. Yield information was obtained from local farmers and county officials. Crop prices used were those required by regulation. A composite damage estimate was arrived at based on crop and damage value per acre. The composite damage per acre was multiplied by average annual acres flooded under with- and without-project conditions to determine average annual damages and benefits.

Table B-3 shows the average dollar damage analysis for corn grown in the Clark County. The estimated average annual damages for crop losses in the study area are \$1,477,000.

## **TRANSPORTATION DAMAGES**

In flood conditions, numerous county roads and bridges would be impassable or unreachable. Average daily traffic counts in 1990 for the six bridges in the study area were obtained and detour costs were determined. Four of the six bridges were constructed sometime around 1910, are low, and would necessitate that their normal traffic be detoured during high water stages.

Once overtopped, traffic would not be allowed on the bridges until after the water had receded and the ground had the opportunity to stabilize. It was assumed that, as a bridge becomes impassable, its traffic would divert to the closest bridge. Bridge elevations were taken from USGS quadrangle sheets. Frequencies for those elevations were derived from flood profiles in Appendix A-Hydrology and Hydraulics. Table B-4 shows the county bridges, their elevation, the flood frequency at which they would overtop, their daily traffic count, and the assumed bridge to which their traffic would detour.

Table B-3 Damage Value Per Acre - Corn

AVERAGE ANNUAL DAMAGES: CORN													
PROJECT: NAYAONDA RIVER BASIN													
STATE: MISSOURI		COUNTY: CLARK											
CURRENT													
PRODUCTION PRICE LEVEL: Apr 91		YIELD / ACRE:		115.0	Bushels	NORMALIZED PRICE:		1.96	per Bushel				
	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SPT	OCT	NOV	DEC	TOTAL
Total Variable Costs (1)	0.74	0.74	0.74	24.12	96.47	30.14	4.84	0.67	13.93	13.93	9.52	0.74	196.58
Expended	0.74	1.48	2.21	26.33	122.80	152.95	157.79	158.45	172.39	186.32	195.84		196.58
Unexpended	195.84	195.10	194.36	170.25	73.77	43.63	38.79	38.12	24.19	10.25	0.74		0.00
									(3)	(3)	(3)		
Gross Cash Yield (2)	-	-	225.40	225.40	225.40	225.40	225.40	225.40	225.40	135.24	45.08		
Crop Loss (4)	0.00	0.00	31.04	55.15	151.63	181.77	186.61	187.28	170.07	89.42	22.34		
Acreage Planted			0	60%	95%	100%							
Replanting:				(5)	(6)	(8)							
Added expense				14.27	74.57	137.88							
Expected reduced yield				0.00	11.27	101.43							
Adjusted Crop Loss (7)	0	0	0.00	14.27	214.92	218.22	186.61	187.28	170.07	89.42	22.54		
Damage Factor (9)	4%	3%	8%	10%	11%	12%	14%	9%	10%	9%	5%	5%	1.00
Damages per Acre	0	0	0.00	1.43	23.93	26.10	25.71	17.45	17.71	7.81	1.04	0.00	
AVERAGE ANNUAL DAMAGES PER ACRE													\$121.19
(1) Firm Enterprise Data System, National Economic Div., ERS out of Oklahoma State University, Stillwater, Ok: Total Costs for the State of Missouri: Costs of Production (1983 - updated to indicated price level and data from Doane's Agriculture Report Vol. 54, No. 11-5, dated 3/15/91, and Crop Prod. Costs, p. 103.)													
(2) Average Yield in Bushels/Acre * Normalized Price.													
(3) Five-year Average Harvest Times: 40% by Sept; 80% by Oct; 100% by Nov.													
(4) Cash Yield less Unexpended Costs													
(5) 60% acreage planted by Apr 30; 50% Apr average variable costs													
(6) 1/2 May + Apr average variable cost; crop yield reduced by 5%.													
(7) Crop Loss + Added Expense for Replanting													
(8) 1/2 June + May + April average variable costs; crop reduced 45%. No replanting in July, so floods from July on result in Total Crop Loss.													
(9) Damage Factor is the percent of expected total runoff occurring in a given month.													

TABLE B-4

*Bridges in the Study Area*

<u>Bridge</u>	<u>Elevation</u>	<u>Overtopped at Flood Frequency</u>	<u>Daily Traffic Count</u>	<u>Detour to Bridge</u>
County No. 264	580	25%	75	257
County No. 358	575	10%	92	257
County No. 367	570	8%	100	Hwy D
County No. 238	606	3.5%	150	Hwy D
County No. 257	588	2%	88	Hwy D
State Road "D"	599	0.7%	<u>126</u>	Hwy 61

631

Detour mileage for the above impassable roads was determined, with the most direct detour routes used to compute the transportation damages. This report will set out the detailed analysis performed for County Bridge 264. A similar analysis was done for each of the above bridges to determine the total detour and opportunity costs. Table B-5 shows the traffic detour days on an annual basis by various traffic categories for County Bridge 264.

TABLE B-5

*Annual Number of Trips*

<u>Vehicle Type</u>	<u>Annual Detour Days</u>	<u>Average Daily Number of Trips</u>	<u>Total Annual Number of Trips</u>
Passenger Cars	365	70	25,550
School Buses	180	5	900
Mail Vehicles	302	1	302
Farm Machinery	129	2	258
Emergency Vehicles	365	1	365

Total Number of Trips 27,375

Daily Traffic Count = 78 x 365 days per year = 27,375

The 1990 average operating cost per mile for passenger cars was \$0.21, and for all trucks was \$0.61. Operating costs for farm machinery were obtained from Doane's Agricultural Reporting Service. Total detour mileage costs for County Bridge 264 for the 2.3-mile one-way detour are shown in table B-6.

TABLE B-6

*Vehicle Operating Costs for a 1-Year, 2.3-Mile Detour*

<u>Vehicle Type</u>	<u>Total Annual Number of Trips</u>	<u>Operating Cost Per Mile (\$)</u>	<u>Total Additional Operating Cost Per Year (\$)</u>
Passenger Cars	25,550	0.29	16,977
School Buses	900	0.61	1,262
Mail Vehicles	302	0.29	201
Farm Machinery	258	1.02	605
Emergency Vehicles	365	0.61	512
Total Detour Costs			19,557

The opportunity cost of time is the value of work or leisure activities foregone for travel purposes. It is assumed that all farm machinery, mail vehicles, and trucks had one occupant, school buses had a driver and 16 children, and emergency and passenger vehicles had a driver and one passenger. It was assumed that 23 percent of all traffic was leisure related, based upon total county population and total employed persons over the age of 18.

It was assumed that vehicles would be driven at an average of 45 mph and detour times were calculated for each detour route. Detour travel time would be 0.06 of an hour. Opportunity time cost was based on the national average hourly wages for the above occupations based upon U.S. Department of Commerce April 1991 wage rates, adjusted by a factor determined by United States per capita income and the respective county per capita income, as taken from the April 1991 issue of the U.S. Department of Commerce, *Survey of Current Business*.

Wages used for the various drivers were \$9.53 per hour for trucks, \$10.89 for mail vehicles, \$7.78 for emergency vehicles, \$5.66 for school buses, and \$5.76 for farm machinery. Passenger car driver's wages of \$7.07 are the average of the general hourly wage rate and the average hourly minimum wage. For passenger cars, the value of time was assumed to equal one-third of the average hourly wage. This was further adjusted to reflect that 25 percent of Clark County residents are under age 18, making the hourly opportunity cost of time for passenger cars \$2.05. Table B-7 shows the opportunity time costs for a 1-year, 0.06-mile detour.

TABLE B-7

*Opportunity Time Costs for a 1-Year, 0.06-Mile Detour*

<u>Vehicle Type</u>	<u>Total Annual Number of Trips</u>	<u>Opportunity Time Cost Per Hour</u>	<u>Opportunity Time Cost Per Year (\$)</u>
Passenger Cars	25,550	\$ 2.05	3,012
School Buses	900	22.66	1,173
Mail Vehicles	302	10.89	189
Farm Machinery	258	5.76	85
Emergency Vehicles	365	9.53	200
Total Opportunity Costs			4,659

Total detour and opportunity time costs are \$24,216. Annualized at 8-3/4 percent, average annual detour opportunity costs for all drivers are \$2,151 for closure of County Bridge 264 by a 4-year flooding event. Traffic from this bridge would use County Bridge 257, which would close because of being overtopped by a 50-year flooding event. This would result in an additional 0.04-mile detour for these vehicles, increasing their detour and opportunity costs to \$40,009, or \$3,554. Overtopping of that bridge would necessitate detour of this traffic to State Highway "D," incurring an additional 0.65-mile detour for total costs of \$313,800, or \$27,874 annualized.

A similar analysis was done for each of the bridges that would be closed because of flooding by the Wyaconda River. Total annualized damages were \$176,000.

**ROAD REPAIRS**

In addition to the above would be the cost of repairing shoulders and embankments. At current price levels, it would cost \$600/mile for paved surface roadways, \$500/mile for gravel-topped or dirt roadways, and \$1,000/mile for township roads. State of Missouri County Highways maps were used to determine the miles of roads which would be affected in the study area. Total cost of repair and grading would be \$551,000, or \$49,000 annualized at an 8-3/4 percent discount rate.

## ALTERNATIVES

Eight alternatives were formulated for the study area. Six alternatives were eliminated from further consideration in an initial screening. Two alternative methods of protection were analyzed in detail. The first alternative was to provide protection to the study area by construction of a diversion channel. The second alternative was to separate the study area into 12 reaches, 6 on each side of the river, and to construct a levee for each reach. Both alternatives examined providing 10-, 100-, and 500-year levels of protection.

## AVERAGE ANNUAL DAMAGES AND BENEFITS

Average annual benefits are the differences in damages "without project" and "with project." In addition to inundation reduction, benefits may be taken for a more intensive or improved use of the land and for employment of unemployed or underemployed individuals during construction of a project.

### LOCATION BENEFITS

Location benefits are derived from the increased value of the land because of its location in the project area, separate and apart from any increase in value due to normal market increases. Local sources were consulted on the potential for an increase in agricultural land value if 100-year flood protection were provided. It was felt that there would be a nominal \$200 to \$300 increase in land value if flood protection were provided to a 100-year or better flooding event. With an average increase of \$250 for the 9,200 acres of land, the annualized benefit would be \$588,000.

### INTENSIFICATION BENEFITS

Intensification benefits are allowable if the protection afforded by the project would allow a more intensive use of the agricultural land. For instance, if the project allowed a farmer to grow crops on land that had previously been used for growing hay, or merely used for pasture purposes, the increased production capabilities are calculated for the intensification benefit.

The project would affect 9,200 acres of land, the majority of which already is in crop production. It is assumed that some farmers would be able to more intensively use their acreage, but the overall crop production change would be minimal.

## REDEVELOPMENT BENEFITS

None of the counties in the Wyaconda River main stem study area qualify as an area with substantial and persistent unemployment. No redevelopment benefits are allowable.

## DIVERSION CHANNEL

Average annual damages and benefits for providing a 10-, 100-, and 500-year level of protection by constructing a diversion channel for the study area are shown in table B-8.

TABLE B-8

*Average Annual Damages and Benefits-Diversion Channel  
July 1991 Price Levels (in \$1,000's)*

	Average Annual Damages	Average Annual Benefits Level of Protection		
		<u>10-Year</u>	<u>100-Year</u>	<u>500-Year</u>
Agriculture	\$160	\$117	\$153	\$159
Roads	49	19	35	49
Detour	176	35	152	176
Location Benefit	<u>0</u>	<u>40</u>	<u>176</u>	<u>204</u>
Total	\$385	\$211	\$516	\$588

## AVERAGE ANNUAL COSTS

Construction costs and operation and maintenance costs detailed in this report are at July 1991 price levels. Cost figures do not include lands, easements, and rights-of-way; interior drainage facilities; or environmental mitigation. Interest during the various construction periods and annualized costs were computed at 8-3/4 percent for a 50-year period of analysis. Table B-9 summarizes the interest calculations during the 3-year construction period.

TABLE B-9

*Interest During Construction-Diversion Channel  
July 1991 Price Levels (in \$1,000's)*

<u>Year</u>	<u>Cost</u>	<u>Time to Base Year</u>	<u>Period</u>	<u>Interest Factor</u>	<u>Interest</u>
10-Year Project					
1	\$ 6,700.0	2.5	(5)	0.23331	\$1,563.0
2	6,700.0	1.5	(3)	0.13408	898.0
2.5	6,700.0	0.5	(1)	0.04283	287.0
	\$20,100.0				\$2,748.0
100-Year Project					
1	\$ 6,900.0	2.5	(5)	0.23331	\$1,610.0
2	6,900.0	1.5	(3)	0.13408	925.0
2.5	6,900.0	0.5	(1)	0.04283	296.0
	\$20,700.0				\$2,831.0
500-Year Project					
1	\$ 7,267.0	2.5	(5)	0.23331	\$1,696.0
2	7,267.0	1.5	(3)	0.13408	974.0
2.5	7,266.0	0.5	(1)	0.04283	311.0
	\$21,800.0				\$2,981.0

Table B-10 shows the average annual costs for providing a 10-, 100-, and 500-year level of protection.

TABLE B-10

*Average Annual Costs-Diversion Channel  
July 1991 Price Levels (in \$1,000's)*

	<u>10-Year</u>	<u>100-Year</u>	<u>500-Year</u>
Project Costs	20,100	20,700	21,800
Interest During Construction	2,749	2,831	2,981
Total First Cost	22,849	23,531	24,781
Interest and Amortization	2,030	2,090	2,202
Operations and Maintenance	3	3	3
Total Average Annual Cost	2,033	2,093	2,205



## ECONOMIC SUMMARY

Table B-11 presents the summary economic analysis for construction of the diversion channel alternative considered in this report.

TABLE B-11

*Economic Analysis Summary-Diversion Channel  
July 1991 Price Levels (in \$1,000's)*

	Level of Protection		
	<u>10-Year</u>	<u>100-Year</u>	<u>500-Year</u>
Total First Cost	\$22,849	\$23,531	\$24,781
Average Annual Cost	2,033	2,093	2,205
Average Annual Benefit	171	340	384
Net Benefits	\$(1,861)	\$(1,753)	\$(1,820)
Benefit-to-Cost Ratio	0.08	0.16	0.17

## LEVEES

Average annual damages from existing conditions and benefits from providing levee protection to a 10-, 100-, and 500-year flooding event were determined for each of the 12 reaches. Table B-9 shows the total average annual damages and benefits for each of the 12 reaches. "L" refers to the left bank and "R" to the right bank of the river (see plate 1 of the main report). The respective columns are not totalled, as comparing the totals in tables B-8 and B-12 would be misleading. When looked at separately by reach, the transportation damages are assigned to each side of the river if the bridge is impassable, resulting in an increase in the overall total damages and benefits.

TABLE B-12

*Average Annual Damages and Benefits-Levees  
1991 Price Levels (in \$1,000's)*

	Average Annual Damages	Average Annual and Location Benefit Level of Protection								
		10-	Int.	Total	100-	Int.	Total	500-	Int.	Total
L-1	11	5	13	18	9	22	31	11	22	33
L-2	45	18	7	25	36	14	50	45	18	63
L-3	30	4	9	13	25	11	36	30	11	41
L-4	36	25	12	37	34	14	48	36	14	50
L-5	34	25	10	35	31	13	44	34	13	47
L-6	78	44	9	53	73	13	86	78	13	91
R-1	8	2	7	9	4	11	15	8	11	19
R-2	48	19	7	26	41	13	54	48	13	61
R-3	8	6	8	14	8	11	19	8	11	19
R-4	66	36	28	64	62	31	93	66	32	8
R-5	49	39	14	53	46	17	63	49	17	66
R-6	110	71	23	94	104	28	132	110	28	138

To determine whether constructing levees to protect any or all of the 12 separable reaches is economically feasible, interest during construction and average annual costs were computed for each of the 12 reaches for the same 3 levels of protection. Tables B-13 through B-15 show these summaries.

As indicated by these tables, none of the alternatives studied are economically feasible. As a Federal interest has not been determined, no Financial Impact to Local Sponsors or Ability to Pay Analysis are included.

#### SENSITIVITY ANALYSIS

Many small streams are located throughout the study basin. Road crossings over these streams vary from none to simply a gravel base. No analysis was done on repair of damage to these road crossings or estimation of detour costs.

For this economic analysis, ground elevations and bridge elevations were based upon USGS quadrangle maps which indicated the major bridge elevations. All other elevations were determined using these quadrangle maps which necessitated interpreting from 20-foot contours.

Table B-13  
Interest During Construction  
July 1991 Price Levels - In Thousands

Reach	Level of Protection	Project First Costs	Years	Period to Base Year	Factor	Interest	TOTAL PROJECT COSTS
L1 Levee	10-yr	1,480	1	0.5	0.04283	63.4	1543
	100-yr	2,480	1	0.5	0.04283	106.2	2586
	500-yr	4,240	1	0.5	0.04283	181.6	4422
L2 Levee	10-yr	1,200	1	0.5	0.04283	51.4	1251
	100-yr	2,300	1	0.5	0.04283	98.5	2399
	500-yr	3,380	1	0.5	0.04283	144.8	3525
L3 Levee	10-yr	2,160	1	0.5	0.04283	92.5	2253
	100-yr	3,210	1	0.5	0.04283	137.5	3347
	500-yr	3,800	1	0.5	0.04283	162.8	3963
L4 Levee	10-yr	1,860	1	0.5	0.04283	79.7	1940
	100-yr	2,400	1	0.5	0.04283	102.8	2503
	500-yr	3,080	1	0.5	0.04283	131.9	3212
L5 Levee	10-yr	1,350	1	0.5	0.04283	57.8	1408
	100-yr	2,020	1	0.5	0.04283	86.5	2107
	500-yr	2,700	1	0.5	0.04283	115.6	2816
L6 Levee	10-yr	2,540	1	0.5	0.04283	108.8	2649
	100-yr	4,100	1	0.5	0.04283	175.6	4276
	500-yr	5,880	1	0.5	0.04283	251.9	6132
R1 Levee	10-yr	1,630	1	0.5	0.04283	69.8	\$1,700
	100-yr	2,600	1	0.5	0.04283	111.4	2,711
	500-yr	4,100	1	0.5	0.04283	175.6	4,276
R2 Levee	10-yr	1,380	1	0.5	0.04283	59.1	1,439
	100-yr	2,680	1	0.5	0.04283	114.8	2,795
	500-yr	3,840	1	0.5	0.04283	164.5	4,004
R3 Levee	10-yr	1,520	1	0.5	0.04283	65.1	1,585
	100-yr	2,540	1	0.5	0.04283	108.8	2,649
	500-yr	3,710	1	0.5	0.04283	158.9	3,869

Table B-13 - Continued

Reach	Level of Protec- tion	Project First Costs	Years	Period to Base Year	Factor	Interest	TOTAL PROJECT COSTS
~~~~~	~~~~~	~~~~~	~~~~~	~~~~~	~~~~~	~~~~~	~~~~~
R4 Levee	10-yr	8,290	2	1.5	0.13408	555.8	
				0.5	0.04283	177.5	9,023
	100-yr	11,500	2	1.5	0.13408	771.0	
				0.5	0.04283	246.3	12,517
	500-yr	13,800	2	1.5	0.13408	925.2	
				0.5	0.04283	295.5	15,021
R5 Levee	10-yr	4,590	2	1.5	0.13408	307.7	
				0.5	0.04283	98.3	4,996
	100-yr	6,630	2	1.5	0.13408	444.5	
				0.5	0.04283	142.0	7,216
	500-yr	8,920	2	1.5	0.13408	598.0	
				0.5	0.04283	191.0	9,709
R6 Levee	10-yr	3,190	1	0.5	0.04283	136.6	3,327
	100-yr	5,580	1	0.5	0.04283	239.0	5,819
	500-yr	8,380	1	0.5	0.04283	358.9	8,739

Table B-14  
Average Annual Costs  
July 1991 Price Levels - In Thousands

Reach	Level of Protection	Project First Costs	Interest During Construc.	TOTAL FIRST COSTS	I and A At 8-3/4%	O & M	Total Average Annual Cost
L1 Levee	10-yr	1,480	63.4	1,543	137	0.5	138
	100-yr	2,480	106.2	2,586	230	0.5	230
	500-yr	4,240	181.6	4,422	393	0.5	393
L2 Levee	10-yr	1,200	51.4	1,251	111	0.5	112
	100-yr	2,300	98.5	2,399	213	0.5	214
	500-yr	3,380	144.8	3,525	313	0.5	314
L3 Levee	10-yr	2,160	92.5	2,253	200	0.5	201
	100-yr	3,210	137.5	3,347	297	0.5	298
	500-yr	3,800	162.8	3,963	352	0.5	353
L4 Levee	10-yr	1,860	79.7	1,940	172	0.5	173
	100-yr	2,400	102.8	2,503	222	0.5	223
	500-yr	3,080	131.9	3,212	285	0.5	286
L5 Levee	10-yr	1,350	57.8	1,408	125	0.5	126
	100-yr	2,020	86.5	2,107	187	0.5	188
	500-yr	2,700	115.6	2,816	250	0.5	251
L6 Levee	10-yr	2,540	108.8	2,649	235	0.6	236
	100-yr	4,100	175.6	4,276	380	0.6	380
	500-yr	5,880	251.9	6,132	545	0.6	545
R1 Levee	10-yr	1,630	69.8	\$1,700	151	0.75	152
	100-yr	2,600	111.4	2,711	241	0.75	242
	500-yr	4,100	175.6	4,276	380	0.75	381
R2 Levee	10-yr	1,380	59.1	1,439	128	0.5	128
	100-yr	2,680	114.8	2,795	248	0.5	249
	500-yr	3,840	164.5	4,004	356	0.5	356
R3 Levee	10-yr	1,520	65.1	1,585	141	0.5	141
	100-yr	2,540	108.8	2,649	235	0.5	236
	500-yr	3,710	158.9	3,869	344	0.5	344

Table B-14 - Continued

Reach	Level of Protection	Project First Costs	Interest During Construc.	TOTAL FIRST COSTS	I and A At 8-3/4%	O & M	Total Average Annual Cost
R4 Levee	10-yr	8,290	555.8 177.5	9,023	802	2.0	804
	100-yr	11,500	771.0 246.3	12,517	1112	2.0	1114
	500-yr	13,800	925.2 295.5	15,021	1334	2.0	1336
R5 Levee	10-yr	4,590	307.7 98.3	4,996	444	1.0	445
	100-yr	6,630	444.5 142.0	7,216	641	1.0	642
	500-yr	8,920	598.0 191.0	9,709	863	1.0	864
R6 Levee	10-yr	3,190	136.6	3,327	296	1.0	297
	100-yr	5,580	239.0	5,819	517	1.0	518
	500-yr	8,380	358.9	8,739	776	1.0	777

Table B-15  
Economic Analysis Summary  
July 1991 Price Levels - In Thousands

Reach ~~~~~	Level of Protec- tion ~~~~~	Total First Costs ~~~~~	Average Annual Cost ~~~~~	Average Annual Benefit ~~~~~	Net Benefits ~~~~~	Benefit to Cost Ratio ~~~~~
L1 Levee	10-yr	1,543	138	18	(120)	0.13
	100-yr	2,586	230	28	(202)	0.12
	500-yr	4,422	393	31	(362)	0.08
L2 Levee	10-yr	1,251	112	18	(94)	0.16
	100-yr	2,399	214	36	(178)	0.17
	500-yr	3,525	314	46	(268)	0.15
L3 Levee	10-yr	2,253	201	4	(197)	0.02
	100-yr	3,347	298	25	(273)	0.08
	500-yr	3,963	353	30	(323)	0.09
L4 Levee	10-yr	1,940	173	40	(133)	0.23
	100-yr	2,503	223	51	(172)	0.23
	500-yr	3,212	286	54	(232)	0.19
L5 Levee	10-yr	1,408	126	25	(101)	0.20
	100-yr	2,107	188	31	(157)	0.17
	500-yr	2,816	251	34	(217)	0.14
L6 Levee	10-yr	2,649	236	51	(185)	0.22
	100-yr	4,276	380	82	(298)	0.22
	500-yr	6,132	545	87	(458)	0.16
R1 Levee	10-yr	1,700	152	2	(150)	0.01
	100-yr	2,711	241	4	(237)	0.02
	500-yr	4,276	380	8	(372)	0.02
R2 Levee	10-yr	1,439	128	19	(109)	0.15
	100-yr	2,795	249	41	(208)	0.16
	500-yr	4,004	356	48	(308)	0.13
R3 Levee	10-yr	1,585	141	8	(133)	0.06
	100-yr	2,649	236	11	(225)	0.05
	500-yr	3,869	344	11	(333)	0.03

Table B-15 - Continued

Reach	Level of Protection	Total First Costs	Average Annual Cost	Average Annual Benefit	Net Benefits	Benefit to Cost Ratio
R4 Levee	10-yr	9,023	804	69	(735)	0.09
	100-yr	12,517	1114	100	(1,014)	0.09
	500-yr	15,021	1336	104	(1,232)	0.08
R5 Levee	10-yr	4,996	446	58	(388)	0.13
	100-yr	7,216	643	69	(574)	0.11
	500-yr	9,709	865	73	(792)	0.08
R6 Levee	10-yr	3,327	297	133	(164)	0.45
	100-yr	5,819	518	178	(340)	0.34
	500-yr	8,739	777	185	(592)	0.24



200-1000

A

P

P

E

N

PERTINENT CORRESPONDENCE

D

I

X

C

200-1000

RECONNAISSANCE REPORT  
FLOOD CONTROL AND OTHER WATER-RELATED PURPOSES  
WYAGONDA RIVER BASIN, MISSOURI AND IOWA

APPENDIX C  
PERTINENT CORRESPONDENCE

TABLE OF CONTENTS

<u>Subject</u>	<u>Page</u>
Letter from Clark County, Missouri, Commission, December 7, 1987	C-1
Letter from Clark County, Missouri, Commission, July 15, 1988	C-2
Letter from Clark County, Missouri, Commission, June 22, 1989	C-3
Letter from Clark County, Missouri, Commission, June 4, 1990	C-4
Notice of Initiation for Reconnaissance Study, February 5, 1991	C-5
Letter from U.S. Environmental Protection Agency, February 12, 1991	C-7
Letter from U.S. Department of Agriculture, Soil Conservation Service, March 8, 1991	C-9
Letter from U.S. Department of Agriculture, Soil Conservation Service, March 15, 1991	C-10
Letter from Missouri Department of Conservation, March 21, 1991	C-11
Public Open House Notice, mailed May 5, 1991	C-12
Letter from U.S. Congressman Harold Volkmer, May 14, 1991	C-14
Letter from Missouri Department of Conservation, May 24, 1991	C-15
Notice of Study Progress for Reconnaissance Study, July 17, 1991	C-16
Letter from State of Missouri, Department of Natural Resources, July 26, 1991	C-18
Letter from State of Missouri, Department of Conservation, September 18, 1991	C-19
Planning Assistance Letter from U.S. Department of Interior, Fish and Wildlife Service, October 10, 1991	C-20

# Clark County

Leih Ann Hayden  
County Clerk

111 East Court • Kahoka, Missouri 63445  
816-727-3283

## COMMISSIONERS

Wayne J. Blum  
Presiding Commissioner

Charles Allen  
Eastern District

Eddie Brewer  
Western District

December 7, 1987

Pat Burke  
Planning Section  
Army Corps of Engineers  
Clock Tower Building  
Rock Island, Illinois 61201

Dear Mr. Burke:

The Clark County Commission wish to express our concern regarding the flooding on the Wyaconda River.

As a County Commission we are responsible for roads & bridges in the area. In the flood of Sept. - Oct. 1986 we experienced nearly \$150,000.00 in damages to bridges & Roads in that area of our County. Much of this could have been avoided if there had been adequate measures taken to control erosion and water before it reached the main channel. We feel it would be more cost effective to control the water flow before it reaches the main channel than try to control the flow after it gets there.

We wholeheartedly support the study of the Wyaconda River Basin and are willing to do anything we can to help in this study. If we can be of any help to you or your staff please feel free to contact us in this matter.

We are putting together a list of losses that were incurred by farmers in this area and will furnish this as soon as possible. We would ask that this study be concluded as soon as possible. Thank-you for your work in this study of the Wyaconda River Basin.

Sincerely,

  
Presiding Commissioner

  
Eastern District Commissioner

  
Western District Commissioner



Leih Ann Hayden  
County Clerk

111 East Court • Kahoka, Missouri 63445  
816-727-3283

COMMISSIONERS

Wayne J. Blum  
Presiding Commissioner

Charles Allen  
Eastern District

Eddie Brewer  
Western District

July 15, 1988

U.S. Army Corps of Engineers  
Clock Tower Building, P.O. Box 2004  
Rock Island, Illinois 61204-2004

RE: Wyaconda River Basin

Dear Sirs:

This letter is to inform you that the Clark County Commission is willing to support the study of the Wyaconda River Basin and to help in any way that is feasible for the county to do. We will ask the adjoining counties to join in this study also.

Even though the County is not financially able to contribute at this time we are willing to lead the drive to raise money from those involved for these matching funds.

Please keep us informed of the progress of this study so we can start our drive to raise these funds.

Sincerely,

*Leih Ann Hayden*  
Clark County Commission  
Leih Ann Hayden, County Clerk

cc: Lucille Darker  
Herb Schutte

# Clark County

111 East Court • Kahoka, Missouri 63445

Phone: 816-727-3283

Leih Ann Hayden  
County Clerk

Nadine Shannon  
Deputy Clerk

June 22, 1989

U. S. Army Corps of Engineers  
Clock Tower Building  
P.O. Box 2004  
Rock Island, Illinois 61204-2004

RE: Wyaconda River Basin

Dear Sirs:


On July 15, 1988, we sent you a letter about the possibility of funds being made available for a study of the Wyaconda River Basin. We are aware that our request for aid was not approved for the FY1990 Budget. We would like for you to give our request for funds from the FY 1991 Budget, your immediate attention.

This study of the Wyaconda River Basin is very important to the agricultural economy of this area. With our history of past flooding, many acres of valuable cropland have been devastated.

If we may be of any further assistance in obtaining this study of the Wyaconda River Basin, please contact us at the address above.

Thanking you in advance, we remain

Cordially yours,



Wayne J. Blum  
Clark County Presiding Commissioner

cc: Lucile Danker

## COMMISSIONERS

Charles Allen  
Eastern District

Wayne J. Blum  
Presiding Commissioner

Eddie Brewer  
Western District

# Clark County

111 East Court • Kahoka, Missouri 63445

Phone: 816-727-3283

Leih Ann Hayden  
County Clerk

June 4, 1990

U. S. Army Corps of Engineers  
Clock Tower Building  
P.O. Box 2004  
Rock Island, Illinois 61204-2004

RE: Wyaconda River Basin

ATTN: Planning Division

Dear Sir:


This letter is to inform you that the Clark County Commission is still very interested in getting a flood control study on the Wyaconda River Basin. This study would help the area farmers in this drainage area.

We have tried for several years to get this project started, but so far we have not been successful. We, the Clark Commission, would like to remind you that we give our support to this project and we will help in any way that is feasibly possible.

We would like to be kept informed of any new developments concerning the Wyaconda River Basin study.

Please feel free to contact us if you have any questions.

Sincerely,



Wayne J. Blum  
Clark County Presiding Commissioner

WJB/lah

## COMMISSIONERS

Charles Allen  
Eastern District

Wayne J. Blum  
Presiding Commissioner

Eddie Brewer  
Western District



REPLY TO  
ATTENTION OF

DEPARTMENT OF THE ARMY  
ROCK ISLAND DISTRICT, CORPS OF ENGINEERS  
CLOCK TOWER BUILDING—P.O. BOX 2004  
ROCK ISLAND, ILLINOIS 61204-2004

February 5, 1991

Planning Division

**NOTICE OF INITIATION**

Reconnaissance Study  
for  
Flood Control and Other Water-Related Purposes

Wyaconda River Basin  
Missouri and Iowa

The Rock Island District of the U.S. Army Corps of Engineers has initiated a reconnaissance study for flood control and other water-related purposes in the Wyaconda River Basin, Missouri and Iowa, with particular reference to Clark and Lewis Counties, Missouri. This study was authorized on September 23, 1987, by resolution of the Committee on Public Works and Transportation, U.S. House of Representatives.

The Wyaconda River Basin encompasses an area of 458 square miles and is about 70 miles long and 8 miles at its greatest width. The river's headwaters are located in Davis County, Iowa, and flow southeast to enter the Mississippi River at La Grange, Missouri. The study area is shown on the enclosed map.

The purpose of this reconnaissance study is to define problems and opportunities in the Wyaconda River Basin and identify potential solutions; determine whether there is a Federal interest in further studies (feasibility phase), based on cost, benefits, and environmental impacts of the identified potential solutions; and assess the non-Federal level of interest and support in the identified potential solutions.

The problems to be addressed in the study include flood induced physical damage to crops, property, and roadways.

Throughout the study process, the Corps of Engineers will coordinate with the States of Missouri and Iowa, including all correspondence, in accordance with Executive Order 12372.

Your knowledge of problems and opportunities in the study area are important to the reconnaissance study. Our Study Manager is Mr. George F. Gitter, Flood Control and Special Studies Branch, Planning Division. He may be reached at telephone 309/788-6361, Ext. 6387. Any information you may have regarding this study, as well as comments or concerns, may be sent to the following address:

District Engineer  
U.S. Army Engineer District, Rock Island  
ATTN: Planning Division (George Gitter)  
Clock Tower Building - P.O. Box 2004  
Rock Island, Illinois 61204-2004

As part of the public involvement process, you will be kept informed of significant study findings.

Sincerely,



John R. Brown  
Colonel, U.S. Army  
District Engineer

Enclosure





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION VII  
726 MINNESOTA AVENUE  
KANSAS CITY, KANSAS 66101

February 12, 1991

Colonel John R. Brown, USA  
U.S. Army Engineer District, Rock Island  
ATTN: Planning Division  
Clock Tower Building - P.O. Box 2004  
Rock Island, Illinois 61204-2004

Dear Colonel Brown:

This is in response to your Notice of Initiation of the Reconnaissance Study for flood control and other water-related purposes for the Wyaconda River Basin, Missouri and Iowa.

A review of our CERCLIS (abandoned, inactive or uncontrolled hazardous waste sites) data current as of January 4, 1991, listed the following sites in the project area and their status:

<u>Site</u>	<u>Status</u>
MOD000687475 Gardner-Denver Company North Main Street La Grange, Missouri 63448	Preliminary assessment (PA) complete; no further action needed under CERCLA; regulated by RCRA
IAT200010346 Amoco Fertilizer Plant W Karr Avenue Bloomfield, Iowa 52537	PA complete; no further action needed under CERCLA
IA0980688345 Bloomfield Foundry Inc. Karr Avenue Bloomfield, Iowa 52537	PA complete; no further action needed under CERCLA; regulated by RCRA
IAD022027668 Hoskins Elevator Warehouse Rt. 6 Bloomfield, Iowa 52537	PA complete; need for further action undetermined
IAD980630495 Van Buren County Landfill RFD Douds, Iowa 52551	PA complete; no further action needed under CERCLA


IAD984566216  
Gire Farm Service  
Highway 98  
Douds, Iowa 52551

PA complete; no further action needed  
under CERCLA

We note also that National Wetland Inventory maps are available for the five county study area and should be consulted for the presence of wetlands.

Thank you for the opportunity to comment. Any questions on these comments can be directed to Mr. Mike Bronoski of my staff at 913/551-7291.

Sincerely,



Lawrence M. Cavin  
Chief, Environmental Review  
and Coordination Section



United States  
Department of  
Agriculture

Soil  
Conservation  
Service

210 Walnut Street  
693 Federal Building  
Des Moines, Iowa 50309

March 8, 1991

Colonel John R. Brown  
U.S. Army District Engineer  
Department of the Army  
Rock Island District  
Corps of Engineers  
Clock Tower Building  
P.O. Box 2004  
Rock Island, Illinois 61204-2004

Dear Colonel Brown:

The Notice of Initiation for a reconnaissance study for flood control and other related purposes regarding the Wyaconda River Basin, Missouri and Iowa has been reviewed by my staff.

It is important you are aware of the following: The South Wyaconda River was studied by the Soil Conservation Service and a plan totally implemented in the 36,255 acre watershed. An application for PL-566 assistance was approved in April 1957 with construction completed in 1979.

You should also be aware that a request to study the North Wyaconda is on file. This request includes Davis and Van Buren Counties in Iowa and Scotland and Clark Counties in Missouri. The total size of this watershed is 73,500 acres, 21,315 acres in Iowa and 52,185 acres in Missouri. This request for assistance was approved in July 1963. The North Wyaconda plan will be prepared by the Soil Conservation Service staff in Missouri.

Public Law 566 authorizes the Soil Conservation Service to prepare plans and provide assistance in watersheds of less than 250,000 acres. The remaining area which requires treatment is well within the criteria for PL-566 assistance. The application we received includes the watershed area to the junction of the South and North Wyaconda. Basically, the Little Wyaconda River, Sugar Creek, and Crooked Creek would be the remaining areas to be studied. These are well within the size criteria of PL-566 and would be quite small for traditional USACOE assistance. We recommend these projects be given further attention through PL-566 if local people feel additional assistance is needed in these areas.

If further information or discussion is required, please feel free to contact James M. Reel, WRPS Leader, at (515) 284-4135.

Sincerely,

Jeffrey R. Vonk  
State Conservationist





United States  
Department of  
Agriculture

Soil  
Conservation  
Service

555 Vandiver Drive  
Columbia, Missouri  
65202

March 15, 1991

Colonel John R. Brown  
District Engineer  
Rock Island District  
Corps of Engineers  
P. O. Box 2004  
Rock Island, Illinois 61204-2004

Dear Colonel Brown:

This is in response to the Notice of Initiation for a reconnaissance study for flood control and related purposes in the Wyaconda River Basin, Missouri and Iowa.


Through the authorities of the Watershed Protection and Flood Prevention Act (Public Law 83-566), the Soil Conservation Service has provided planning and implementation assistance to this basin since the mid-1950's. P.L.-566 authorizes the Soil Conservation Service to provide financial and technical assistance to local sponsors in watersheds of 250,000 acres and less.

At the present time, applications for P.L.-566 assistance have been made by local sponsors on four watersheds within the study area. The South Wyaconda River Watershed (36,255 acres in Iowa) has a completed watershed plan with all measures installed. The Little Wyaconda River-Sugar Creek Watershed (98,958 acres) has a completed plan with partial installation of planned measures.

The North Wyaconda River Watershed (73,500 acres, 21,315 acres in Iowa and 52,185 acres in Missouri) has an active application on file with our office. Some preliminary field information has been collected and at some date when staffing and funding are available we plan to complete the study on North Wyaconda River Watershed.

Please contact Mike Wells, Assistant State Conservationist for Water Resources at 314/875-5213, if the Soil Conservation Service can be of assistance.

Sincerely,

  
ACTING  
RUSSELL C. MILLS  
State Conservationist


cc: Jeffrey R. Vonk, State Conservationist, SCS, Des Moines, IA  
Lynn Kilpatrick, Area Conservationist, SCS, Hannibal, MO

C-10



The Soil Conservation Service  
is an agency of the  
United States Department of Agriculture





# MISSOURI DEPARTMENT OF CONSERVATION

MAILING ADDRESS  
P.O. Box 180  
Jefferson City, Missouri 65102-0180

STREET LOCATION  
2901 West Truman Boulevard  
Jefferson City, Missouri

Telephone: 314/751-4115  
JERRY J. PRESLEY, Director

March 21, 1991

Colonel John R. Brown  
Rock Island District, Corps of Engineers  
Clock Tower Building  
P. O. Box 2004  
Rock Island, Illinois 61204-2004

Attn: Planning Division (George Gitter)

Dear Colonel Brown:

We appreciate the opportunity to provide input into the reconnaissance study for flood control and other water-related purposes in the Wyaconda River basin. It is our view that much can be accomplished in the Wyaconda River basin to restore water quality and provide flood damage reduction. With that in mind, we offer the following general areas of interest to this Department.

1. Environmental - Delineate, restore and protect floodways on Wyaconda River and tributaries in the study area. Measures that would work include reforestation of riparian corridor/floodway, reforest uplands to double the  $\pm 20\%$  forested area, reduce grazing in woodlands and attempt to restore wetlands. Based on historic records, these measures would also reduce flood damage.
2. Erosion - Delineate bank erosion areas and treat the sites with riprap, cedar tree revetment or vegetation such as willow cuttings. Erosion control would reduce sediment input and improve water quality.
3. Flooding - Flood damage reduction by restoration of trees in the floodway. Restoration of wetlands could benefit a wide array of species while providing other benefits.
4. Water Quality - Treat eroding banklines and, where channelization has occurred, restore stream gradient.

We look forward to providing input and insight to this effort. If you or your staff have questions, please contact William H. Dieffenbach of my staff.

Sincerely,

DAN F. DICKNEITE  
ENVIRONMENTAL ADMINISTRATOR

cc: U. S. Fish and Wildlife Service  
Columbia, MO

COMMISSION

JERRY P. COMBS  
Kansas

ANDY DALTON  
Springfield

C-11

JAY HENGES  
St. Louis

JOHN POWELL  
Rolla



Army Corps  
Engineers  
Rock Island District

## WYACONDA RIVER BASIN, MISSOURI AND IOWA, FLOOD CONTROL RECONNAISSANCE STUDY

### OPEN HOUSE

---

#### \*\*\* BACKGROUND \*\*\*

The U.S. Army Corps of Engineers, Rock Island District, is studying the feasibility of measures for flood control and other water related purposes in the Wyaconda River Basin, Missouri and Iowa. The purpose of the study is to define problems and opportunities in the Wyaconda River Basin and to identify potential solutions; determine whether there is a Federal interest in further studies (feasibility phase) based on cost, benefits, and environmental impacts of the identified potential solutions; and assess the non-Federal level of interest and support in the identified potential solutions.

#### \*\*\* PURPOSE OF OPEN HOUSE \*\*\*

The purpose of the open house will be for the Corps of Engineers to gather input from the residents who live in and are familiar with the Wyaconda River Basin. Those attending will have the opportunity to discuss on a one-to-one basis with a Corps of Engineers representative information they may have on water resource problems and needs in the Wyaconda River Basin area.

#### \*\*\* WHEN/WHERE \*\*\*

Monday, May 20, 1991  
1-4 p.m. and 6-8 p.m.

Court House  
Circuit Court Room  
111 East Court  
Kahoka, Missouri




#### \*\*\* WHO IS INVITED \*\*\*

All interested persons are urged to attend the open house. This includes representatives of civic, business, recreation, and conservation groups; property owners; Federal and non-Federal agencies; and the public.

#### \*\*\* FOR MORE INFORMATION \*\*\*

Contact: District Engineer  
U.S. Army Engineer District, Rock Island  
ATTN: Planning Division  
Clock Tower Building  
Rock Island, Illinois 61204-2004

Or Call: Mr. George I. Gitter, Community Planner  
309/788-6361, Ext. 6387



C-13

MISSISSIPPI RIVER  
 WYACONDA RIVER BASIN  
 IOWA & MISSOURI  
 FLOOD CONTROL PROJECT  
 ROCK ISLAND DISTRICT  
 CORPS OF ENGINEERS  
 OCTOBER 1988

HAROLD L. VOLKMER  
9TH CONGRESSIONAL DISTRICT  
MISSOURI

2411 RAYBURN HOUSE OFFICE BUILDING  
WASHINGTON DC 20515  
(202) 225-2956

HOUSE COMMITTEE ON  
AGRICULTURE

HOUSE COMMITTEE ON  
SCIENCE AND TECHNOLOGY

SELECT COMMITTEE ON AGING

# Congress of the United States

House of Representatives

Washington, DC 20515

May 14, 1991

DISTRICT OFFICES  
ROOM 370  
FEDERAL BUILDING  
HANNIBAL MO 63401  
(314) 221-1200

912 E WALNUT  
COLUMBI MO 65206  
(314) 449-5111

122 BOURKE  
MACON MO 63557  
(816) 385-5615

317 LAFAYETTE  
P.O. BOX 229  
WASHINGTON MO 63090  
(314) 239-4001


George Gitter  
Community Planner  
U.S. Army Engineer District  
Attn: Planning Division  
Clock Tower Division  
Rock Island, Illinois 61204-2004

Dear George

Thank you for inviting me to the open house of the Wyaconda River Basin Flood Control Reconnaissance Study. I regret that I will be unable to attend as the House will be in session on May 20th.

I am sure this will be a productive meeting and I appreciate the thoughtful invitation. With kindest regards, I am

Sincerely,



Harold L. Volkmer  
Member of Congress

HLV/pl





## MISSOURI DEPARTMENT OF CONSERVATION

MAILING ADDRESS  
P.O. Box 180  
Jefferson City, Missouri 65102-0180

STREET LOCATION  
2901 West Truman Boulevard  
Jefferson City, Missouri

Telephone: 314/751-4115  
JERRY J. PRESLEY, Director

May 24, 1991

Colonel John R. Brown  
District Engineer  
Rock Island District, Corps of Engineers  
Clock Tower Building  
P.O. Box 2004  
Rock Island, IL 61201

RE: Wyaconda River Reconnaissance Study

Dear Colonel Brown:

We received a copy of your public notice regarding the feasibility study of the Wyaconda River Basin. Members of the Department staff have participated in other study efforts in the basin, including U.S. Department of Agriculture, Soil Conservation Service. As the agency responsible for fish, wildlife and forest resources in Missouri, we would appreciate the opportunity to be involved in this study.

When members of your staff need information or have questions relating to our resource responsibilities, please contact William H. Dieffenbach of my staff.

Sincerely,

*W. H. Dieffenbach*  
for DAN F. DICKNEITE  
PLANNING DIVISION CHIEF

cc: U.S. Fish and Wildlife Service (Columbia, Missouri)

C-15

COMMISSION

JERRY P. COMBS  
Executive Director

ANDY DALTON  
Assistant Director

JAY HENGES  
Sr. Liaison

JOHN PO  
Relia



REPLY TO  
ATTENTION OF

Planning Division

DEPARTMENT OF THE ARMY  
ROCK ISLAND DISTRICT, CORPS OF ENGINEERS  
CLOCK TOWER BUILDING-P.O. BOX 2004  
ROCK ISLAND, ILLINOIS 61204-2004

July 17, 1991

#### **NOTICE OF STUDY PROGRESS**

Reconnaissance Study  
for  
Flood Control and Other Water-Related Purposes

Wyaconda River Basin  
Missouri and Iowa

In December 1990, the Rock Island District of the U.S. Army Corps of Engineers (Corps) initiated a Reconnaissance Study for flood control and other water-related purposes in the Wyaconda River Basin. The authorization gave particular emphasis to Clark and Lewis Counties, Missouri (see attached map). The purpose of this letter is to provide an update of the study's progress.

The early months of the study were spent developing a computer model to calculate flood heights and assessing the nature and extent of flood problems. A field survey was conducted to estimate the amount and type of losses due to flooding, and potential project alternatives were formulated to reduce flood damages. The study is being coordinated with the U.S. Department of Agriculture - Soil Conservation Service (SCS). The SCS has been active in several sub-basin projects in the area.

On May 20, 1991, the Corps conducted an Open House at the County Courthouse in Kahoka, Missouri. The purpose of the Open House was for the Corps to gather information from persons who live in or are familiar with the Wyaconda River Basin.

The Open House was well attended. Approximately 55 Wyaconda Basin farmers, residents, and county representatives discussed their flooding problems with Corps representatives. The attendees were asked either to fill out a comment sheet at the Open House or to take the sheet with them for completion, and then mail it to the Corps' Rock Island District office. Some attendees took extra comment sheets to distribute to those who could not attend.

To date, we have received 32 comment sheets. About 90 percent of those who returned a comment sheet listed flood damage as a major problem. Almost 80 percent are concerned about losses of and damage to crop and pasture land. About 60 percent listed erosion as a problem; 35 percent are concerned about damage to roads and bridges, while almost 25 percent of those who responded listed damage to fences as a problem. Among the other concerns mentioned are the sharp bends of the Wyaconda River, water quality, and the effects of flooding on livestock and wildlife.


We are now assessing the economic viability of levee, channel, and diversion alternatives. Project alternatives move forward based upon a favorable benefit-to-cost ratio. Only project alternatives with economic benefits greater than costs may be considered in the next study phase, which is the feasibility study phase.

We also are working to identify a local sponsor(s) to cost share the feasibility study. A feasibility study is cost shared at 50 percent Federal and 50 percent non-Federal expense. Eligible potential local sponsors include state, county, and local units of government.

If you have any questions or comments about the Wyaconda River Basin Reconnaissance Study, please call Mr. George Gitter of our Flood Control and Special Studies Branch at 309/788-6361, Ext. 6387, or write to the following address:

District Engineer  
U.S. Army Engineer District, Rock Island  
ATTN: Planning Division  
Clock Tower Building - P.O. Box 2004  
Rock Island, Illinois 61204-2004

Sincerely,

  
Dudley M. Hanson, P.E.  
Chief, Planning Division

Attachment

JOHN ASHCROFT  
Governor

G. TRACY MEHAN III  
Director



STATE OF MISSOURI  
DEPARTMENT OF NATURAL RESOURCES

DIVISION OF PARKS, RECREATION, AND HISTORIC PRESERVATION

P.O. Box 176  
Jefferson City, MO 65102  
314-751-2479

Division of Energy  
Division of Environmental Quality  
Division of Geology and Land Survey  
Division of Management Services  
Division of Parks, Recreation,  
and Historic Preservation

July 26, 1991

Mr. Dudley M. Hanson, P.E.  
Chief, Planning Division  
Department of the Army  
Corps of Engineers  
Clock Tower Bldg. P.O. Box 2004  
Rock Island, IL 61204-2004

Dear Mr. Hanson:

This is in response to a "Notice of Study Progress" which was received recently in regard to the Wyaconda River Basin in northeast Missouri.

Enclosed please find a document titled "Canoeing in Northern Missouri" which was developed by the Department of Natural Resources. The Wyaconda River is described as "certainly one of the most beautiful stream corridors in all northern Missouri." Therefore, I would recommend that the study take into consideration the current use of the river for recreation purposes as well.

If we can assist you in any way, please feel free to contact us.

Sincerely,

DIVISION OF PARKS, RECREATION,  
AND HISTORIC PRESERVATION

Wayne E. Gross  
Director

WEG:mdl

Enclosure



## MISSOURI DEPARTMENT OF CONSERVATION

MAILING ADDRESS  
P.O. Box 180  
Jefferson City, Missouri 65102-0180

STREET LOCATION  
2901 West Truman Boulevard  
Jefferson City, Missouri

Telephone: 314/751-4115  
JERRY J. PRESLEY, Director

September 18, 1991

Mr. Dudley M. Hanson  
Chief, Planning Division  
Rock Island District, Corps of Engineers  
P. O. Box 2004  
Rock Island, IL 61204-2004

Re: Wyaconda River Reconnaissance Report

Dear Mr. Hanson:

Members of the Department staff reviewed the "Notice of Study Progress" and other reports dealing with the reconnaissance study you are conducting on part of Wyaconda River. The Department maintains the State Heritage Data Base. Inquiry of that data base yielded the following occurrences of sensitive elements.

Winged mapleleaf mussel (Quadrula fragosa) was recently listed as a federal endangered species. The species is listed as from St. Croix River, Minnesota-Wisconsin. Specimens as recent as 1968 are labeled as being taken from Wayland, Missouri. A search is currently being conducted to ascertain the status of this species in northeast Missouri.


Other species that occur in the vicinity associated with wetlands and river corridors are:

Blanding's turtle ( <u>Emydoidea blandingii</u> )	State Endangered
Western fox snake ( <u>Elaphe vulpina vulpina</u> )	State Endangered
Eastern massasauga ( <u>Sistrurus catenatus catenatus</u> )	State Endangered
Central mudminnow ( <u>Umbra limi</u> )	State Endangered
Dotted Monarda ( <u>monarda punctata</u> )	State Endangered

It is our position to vigorously seek alternatives to channelization. Examples of what channelization has done and continues to inflict on fish and wildlife resources is all too apparent in northeast Missouri.

I hope this letter is of some assistance in your reconnaissance study effort. If you need additional input, please call.

Sincerely,

  
WILLIAM H. DIEFFENBACH  
ASST. PLANNING DIVISION CHIEF

WHD:jct  
cc: U. S. Fish and Wildlife Service

COMMISSION

JERRY P. COMBS  
Kennett

ANDY DALTON  
Springfield

C-19 JAY HENGES  
St. Louis

JOHN POW  
Rolla



IN REPLY REFER TO

## United States Department of the Interior

FISH AND WILDLIFE SERVICE  
Fish and Wildlife Enhancement  
Columbia Field Office  
608 East Cherry Street  
Columbia, Missouri 65201



FWS\FWE-CMFO

OCT 10 1991

Colonel John R. Brown  
District Engineer  
Rock Island District, Corps of Engineers  
Clock Tower Building  
Rock Island, Illinois 61201

Dear Colonel Brown:

This planning assistance letter is submitted by the U.S. Fish and Wildlife Service (Service) to the Rock Island District, U.S. Army Corps of Engineers (Corps) for use in the **Wyaconda River Basin Reconnaissance Study**, in accordance with the provisions of, and under the authority of the Fish and Wildlife Coordination Act (Coordination Act) (48 stat. 401, as amended; 16 U.S.C. 661 et seq.), and the "Agreement Between the U.S. Fish and Wildlife Service and the U.S. Army Corps of Engineers for funding Fish and Wildlife Coordination Activities." Our letter is submitted in accordance with provisions of the Coordination Act, but does not fulfill the reporting requirements of the Service under Section 2(b) of that Act.

The general project area includes Davis and Van Buren Counties, in Iowa, and, Scotland, Clark, and Lewis Counties, in Missouri. However, since the Corps has determined that the reconnaissance study would limit the area of consideration to the reach of the Wyaconda River from the mouth at the Mississippi River to five miles up the North and South branches, this letter identifies fish and wildlife resource problems and needs, and opportunities for only this area. Consequently, the emphasis of this letter will be placed upon Clark and Lewis Counties, Missouri. This letter fulfills the Fiscal Year 1991 Scope-of-Work items for problems, needs, and opportunities input from the Service, as defined in the May 22, 1991, Order for Reimbursable Services (NCR-IA-91-0059).

### Description of the Study Area

The Wyaconda River Basin encompasses an area of approximately 458 square miles and is about 70 miles long and eight miles wide. The River's headwaters are located in Davis County, Iowa, and it flows in a southeasterly direction to empty into the Mississippi River at the town of LaGrange, in Lewis County, Missouri.

Col. John R. Brown  
Wyaconda River Reconnaissance Study

2

The study area is located within the Eastern Glaciated Plains Natural Division (Thom and Wilson, 1980). The soils and topography resulted from the Kansas stage of Pleistocene glaciation. Soils are formed from loess, glacial till, or alluvium along the river bottoms. The pre-settlement, natural vegetation of the area was almost equally divided between forest and prairie, with the prairie areas located primarily in the more level upland, and the forests occupying the slopes and bottomland areas. The floodplains were dominated by forest.

Clark County encompass approximately 327,000 acres, while Lewis County occupies about 324,000 acres. Row crop production takes place on approximately 165,000 acres in Clark County, and 191,000 acres in Lewis County. Forested acres amount to about 62,000 acres in Clark County, and about 41,000 acres in Lewis County. There are about 59,000 grassland acres in Clark County, and 65,000 acres in Lewis County. These figures demonstrate the highly agricultural nature of the study area and the significant changes in land use that have occurred since presettlement times.

The major hydrologic features within Clark County are the Little Fox, Fox, Wyaconda, and Little Wyaconda Rivers. The major drainages in Lewis County are the Wyaconda River, and its tributary Sugar Creek, and the North and Middle Fabius Rivers. The headwaters of the majority of these rivers have been channelized, especially in the Wyaconda and Fabius River systems.

### Fish and Wildlife Resources

#### Aquatic

Due to adjacent land uses, and alteration of the stream channel itself, the stream habitats in the study area have been severely degraded. Increased erosion and sedimentation, channelization, elimination of in-stream cover and deep water pools, and increased organic inputs from run-off from cropland and pasture land, have all contributed to a reduction in aquatic species diversity and abundance in the Wyaconda River. The lower approximately 31 miles of the Wyaconda River in Lewis County to the mouth still maintains a meandering channel. Above that point (approximately T.63N., R.7W., section 35), the River has been extensively channelized, with few meanders remaining. Suckers (Catostomids) and small-mouth bass (Micropterus dolomieu) that require cooler, clearer water are no longer present to any degree.

There are at least 52 different fish species found in the Wyaconda River in Clark and Lewis Counties. Common fish species currently found within the entire study area include: orangespotted (Lepomis humilis) and green (L. cyanellus) sunfish, and bluegill (L. macrochirus); channel catfish (Ictalurus punctatus) and yellow bullhead (I. natalis); common carp (Cyprinus carpio); river carpsucker (Carpionodes carpio); central stoneroller (Camptostoma anomalum); red (Notropis lutrensis), emerald (N. atherinoides), and bigmouth (N. dorsalis)

## Wyaconda River Reconnaissance Study

shiners; fathead (Pimephales promelas) and bluntnose (P. notatus) minnows; white (Pomoxis annularis) and black (P. nigromaculatus) crappie; white bass (Morone chrysops); and, largemouth bass (Micropterus salmoides). The lower Wyaconda River in Lewis County supports fish species commonly found in the Mississippi River, such as the freshwater drum (Aplodinotus grunniens), smallmouth (Ictiobus bubalus) and bigmouth (I. cyprinellus) buffalo, redbreast (Moxostoma spp.), and flathead catfish (Pylodictis olivaris).

Terrestrial

The majority of uplands in the study area were at one time covered by pre-settlement prairie, and were dominated by such species as big bluestem (Andropogon gerardii), Indiangrass (Sorghastrum nutans), little bluestem (Shizaciarium scoparium), pale-purple coneflower (Echinacea pallida), and lead plant (A. canescens). Almost all of the native prairie has been converted to fescue pasture or row crops.

Scattered upland forested areas were dominated by white oak (Quercus alba), red oak (Q. rubra), shagbark hickory (Carya ovata), basswood (Tilia americana), and American elm (Ulmus americana). Xeric glades were present as well, with red cedar (Juniperus virginiana) interspersed amongst the prairie plants. Many of the upland forests were harvested, either partially or clear-cut. A large percentage of existing forest land is in poor condition due to previous logging or current cattle grazing.

There is a limited amount of remaining bottomland forest, most of which is scattered in many small parcels along the Wyaconda River and its former channel and tributaries. Typical tree species present include cottonwood (Populus deltoides), black willow (Salix niger), silver maple (Acer saccharinum), sugar maple (A. saccharum), box elder (A. negundo), green ash (Fraxinus pennsylvanica), sycamore (Plantanus occidentalis), and black walnut (Juglans nigra).

The Missouri Natural Areas Inventory (Anderson: 1983) recognized the lower two miles of the Wyaconda River as a "significant area" since the plant communities along the cliff face and the ravines are mostly undisturbed, scattered upland forest and small open glades.

Typical mammalian species that inhabit the study area include the white-tailed deer (Odocoileus virginianus), coyote (Canis latrans), gray fox (Urocyon cinereoargenteus), red fox (Vulpes vulpes), raccoon (Procyon lotor), striped skunk (Mephitis mephitis), opossum (Didelphis virginiana), and gray squirrel (Sciurus carolinensis).

Common avian species in the study area include the American kestrel (Falco sparverius), red headed woodpecker (Melanerpes erythrocephalus), eastern meadowlark (Sturnella magna), eastern kingbird (Tyrannus tyrannus), eastern bluebird (Sialia sialis), field sparrow (Spizella



Col. John R. Brown  
Wyaconda River Reconnaissance Study

4

pusilla), dickcissel (Spiza americana), horned lark (Eremophila alpestris), common flicker (Colaptes auratus), northern oriole (Icterus galbula), mockingbird (Mimus polyglottos), gray catbird (Dumetelia carolinensis), brown thrasher (Toxostoma rufum), green heron (Butorides striatus), and great blue heron (Ardea herodias).

Wetland Resources

A review of the data in the Service's National Wetlands Inventory shows that there are few extensive wetlands within the study area. The largest group of wetlands are associated with the floodplains and bankline of the Wyaconda River and its former channel. The historic floodplain in the upper portion of the River averages about 1 mile wide. However, numerous levees have reduced the functional floodplain considerably in many areas. Wetlands in the floodplain are usually classified as palustrine forested, palustrine scrub-shrub, or palustrine emergent (Cowardin et al. 1979). There are numerous unconsolidated bottom wetlands (i.e., farm ponds) scattered throughout the uplands of the study area, created primarily to provide livestock water.

The highest concentrations of forested wetlands are found along the Wyaconda River in the following areas:

- T.62N., R.6W. sections 17, 21, and 28;
- T.62N., R.7W., section 1;
- T.63N., R.7W., sections 4, 5, 9, 14, 15, 23, 26, and 35;
- T.64N., R.7W., section 31;
- T.64N., R.8W., sections 5, 8, 9, 14, 15, 16, 23, 25;
- T.65N., R.9W., sections 25, 26, 36;

The Soil Conservation Service's wetlands inventory has yielded similar findings to those of the Service's National Wetlands Inventory. The most prominent wetlands identified, in addition to those the Service has mapped, are farmed wetlands. The largest number of farmed wetlands are found in the floodplain of the Wyaconda River.

Col. John F. Brown  
Wyaconda River Reconnaissance Study

5

Endangered Species

In accordance with Section 7(c) of the Endangered Species Act, we have determined that the following federally-listed species may occur in the project area. No designated critical habitat occurs in the project area.

Species	Federal Status <sup>1</sup>	Status in Missouri	County	Habitat
Bald Eagle ( <u>Haliaeetus leucocephalus</u> )	E	Migrant, winter resident, rare breeder along some of the major rivers in the state	Clark Lewis	Large lakes and rivers
Fat pocketbook pearly mussel ( <u>Potamilus capax</u> )	E	Probable in Dunklin Co.; recently introduced into Mississippi River in Pike Co.	Clark Lewis	Large rivers
Higgins' eye pearly mussel ( <u>Lampsilis higginsii</u> )	E	Mainly along Mississippi R. and its tribs.	Clark Lewis	Large rivers
Indiana bat ( <u>Myotis sodalis</u> )	E DCH	Scattered throughout the state designated critical habitat in Crawford Franklin, Iron, Shannon, Washington Co.s	Lewis	Limestone karst caves; forage along riparian corridors and forested hillsides

---

<sup>1</sup> E= Endangered, T= Threatened, PE= Proposed for listing as Endangered, PT= Proposed for listing as Threatened, DCH= Designated Critical Habitat

Col. John R. Brown  
Wyaconda River Reconnaissance Study

6

The preceding table includes federally-listed species that may occur in the project area, and does not constitute consultation nor fulfill requirements under Section 7(a)(2) of the Endangered Species Act of 1973, as amended. When specific project information is made available, we will be able to provide more detailed comments. If the U.S. Army Corps of Engineers determines that a project may affect listed species, formal or informal consultation should be requested with this office.

Bald eagles have become more common nesters in Missouri, largely because of increased management efforts. However, the greatest number of eagles occur in spring and winter when migrating birds spend several weeks in Missouri. They concentrate around open bodies of water, usually perching or roosting in tall trees that line river banks.

The Indiana bat is a permanent resident of Missouri. It usually winters in caves. However, during the spring and summer months, the females congregate in maternity colonies under the loose bark of trees. The Indiana bat forages extensively along riparian areas and over streams.

The fat pocketbook and 'Jiggins' eye pearly mussels are not found in the project area, but do occur in the Mississippi River immediately downstream.

### Fish and Wildlife Resource Problems and Needs

#### Aquatic

As mentioned above, the upper portion of the Wyaconda River has been extensively channelized. As a result, the river has lost approximately 50 percent of its length. Consequently, at least 50 percent of the aquatic habitat has been lost.

The available suitable habitat within the existing channelized river has been degraded as well. The remnant oxbows have been filled in or silted in, and no longer can function as spawning and temporary water storage areas. The loss of aquatic resources, both quantitatively and qualitatively, has been much greater than the physical loss of half of the pre-channelized configuration.

Channelization has resulted in loss of in-stream cover, elimination of deeper pool habitat in the upper reaches, increased water velocities upstream, and increased sedimentation downstream. Conversion of native prairie and forest land to agriculture has contributed to increased sedimentation, and increased levels of organic chemicals entering the watershed, degrading the water quality.

### Terrestrial

Over half of the forested habitat in the River basin, especially in the floodplain of the Wyaconda River, has been eliminated. Reduction and removal of forested riparian areas has adversely affected the habitats of the great blue heron, green heron, river otter (Lutra canadensis), mink (Mustela vison), and other species. Such activities have contributed to the loss of suitable habitat for the federally-listed Indiana bat. Native prairie has been plowed for row crop production or planted to fescue pasture. These activities have significantly reduced wildlife habitat diversity, breeding habitat, and cover.

### Wetland Resources

Channelization and the construction of levees to attempt to control flooding, have allowed the forested wetlands of the floodplains to be cleared for agricultural purposes. Drainage ditches, filling of scour areas and old oxbows, and land leveling also have contributed to wetland losses.

These activities have reduced flooding upstream while increasing flooding downstream. However, downstream flooding is probably not as frequent as it once was, but it is of greater magnitude when flood events do occur. This alteration of hydrology has further degraded the remaining wetlands, especially depressional areas that are not recharged as frequently by flooding.

### Conclusions and Recommendations

This planning aid letter has presented a general description of the project area, and some of the major natural features and fish and wildlife resources present. Land-use changes and their impacts to natural aquatic, terrestrial, and wetland communities have been discussed.

The following recommendations are provided to assist the Corps in developing a project proposal for the Wyaconda River basin flood control study that would benefit fish and wildlife and their habitats:

- since channelization already has resulted in the loss of tens of miles of riparian habitat in the project area, we discourage any additional channelization attempts, as they would probably only exacerbate existing problems.
- the construction of unified levees along the channelized or the downstream portion of the Wyaconda River would further constrict the floodplain and potentially create

Col. John R. Brown

8

Wyaconda River Reconnaissance Study

flooding problems upstream of such construction. A further reduction in the floodplain would contribute to even greater wetland losses in the area.

-re-establishment of the floodplain would provide flood reduction benefits, while also improving fish and wildlife habitats. This may involve levee realignment and further from the river channel in some areas. A larger floodplain would function as a temporary storage area, would allow for the settling out of sediments, enrichment of the soil, would increase groundwater recharge, and would contribute to improved water quality downstream. Fisheries resources and wetland habitats would benefit from connecting the old channel to the channelized portion of the Wyaconda River in areas where significant portions of the old meanders remain.

-aside from the above river channel improvements, adjacent wetlands could be restored through alteration of existing levees and construction of others to impound flood waters and hold run-off. Initiation of a wetland easement/enhancement program, in conjunction with ongoing Section 10/404 and "Swampbuster" regulation, as well as with the Service's and Missouri Department of Conservation's private lands wetland restoration program, could help to preserve and restore wetland resources within the study area.

We appreciate the opportunity to review the proposed project. Should you have questions concerning these comments and recommendations, or if we can be of any further assistance, please contact Richard Szlemp at the address above, or by telephone at (314)876-1911 or (FTS)276-1911.

Sincerely,



Jerry J. Brabander  
Field Supervisor

Col. John R. Brown  
Wyaconda River Reconnaissance Study

9

Literature cited

Anderson, Jane. 1983. Missouri Natural Features Inventory. Addition to the Eight County Natural Features Inventory: Scotland, Clark, Knox, Lewis, Shelby, Marion Counties. 47pp.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep water habitats of the United States. USDI, Fish and Wildlife Service. Washington, D.C. 131pp.

Thom, R.H., and J.H. Wilson. 1980. The natural divisions of Missouri. Transactions of the Missouri Academy of Science, Vol. 14, pp. 9-23.

cc: MDC: Jefferson City, MO (Attn: Dan Dickneite)  
MDC, Jefferson City, MO (Attn: Dennis Figg)

RRS:rs:XC WYACPL

DISTRIBUTION LIST

DISTRIBUTION LIST FOR  
RECONNAISSANCE REPORT  
FLOOD CONTROL AND OTHER WATER-RELATED PURPOSES  
WYACONDA RIVER BASIN, MISSOURI AND IOWA

DISTRIBUTION -- EXTERNAL

REPORT                      NOTICE

HONORABLE CHRISTOPHER BOND, UNITED STATES SENATOR 293 RUSSELL SENATE OFFICE BLDG, WASHINGTON DC 20510-2503	X
HONORABLE JOHN C. DANFORTH, UNITED STATES SENATOR 249 RUSSELL SENATE OFFICE BLDG, WASHINGTON DC 20510-2502	X
HONORABLE CHARLES E. GRASSLEY, UNITED STATES SENATOR 135 HART SENATE OFFICE BLDG, WASHINGTON DC 20510-1501	X
HONORABLE TOM HARKIN, UNITED STATES SENATOR 351 HART SENATE OFFICE BLDG, WASHINGTON DC 20510-1502	X
HONORABLE CHARLES E. GRASSLEY, UNITED STATES SENATOR 206 FEDERAL BUILDING, 101 FIRST STREET, SE CEDAR RAPIDS, IA 52401	X
HONORABLE CHARLES E. GRASSLEY, UNITED STATES SENATOR 721 FEDERAL BUILDING, 210 WALNUT STREET DES MOINES, IA 50309	X
HONORABLE TOM HARKIN, UNITED STATES SENATOR 733 FEDERAL BUILDING, 210 WALNUT STREET DES MOINES IA 50309	X
HONORABLE CHRISTOPHER BOND, UNITED STATES SENATOR 312 MONROE STREET, JEFFERSON CITY MO 65101	X
HONORABLE JOHN C DANFORTH, UNITED STATES SENATOR 1233 JEFFERSON STREET, JEFFERSON CITY MO 65101	X
HONORABLE JIM LEACH, HOUSE OF REPRESENTATIVES 1514 LONGWORTH HOUSE OFFICE BLDG, WASHINGTON DC 20515-1501	X
HONORABLE HAROLD L. VOLKMER, HOUSE OF REPRESENTATIVES 2411 RAYBURN HOUSE OFFICE BLDG, WASHINGTON DC 20515-2509	X
HONORABLE JIM LEACH, REPRESENTATIVE IN CONGRESS PARKVIEW PLAZA, ROOM 204, 107 EAST 2ND STREET OTTUMWA IA 52501	X

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED



DISTRIBUTION LIST FOR  
RECONNAISSANCE REPORT  
FLOOD CONTROL AND OTHER WATER-RELATED PURPOSES  
WYACONDA RIVER BASIN, MISSOURI AND IOWA

DISTRIBUTION -- EXTERNAL

	<u>REPORT</u>	<u>NOTICE</u>
HONORABLE CHRISTOPHER BOND, UNITED STATES SENATOR 293 RUSSELL SENATE OFFICE BLDG, WASHINGTON DC 20510-2503	X	
HONORABLE JOHN C. DANFORTH, UNITED STATES SENATOR 249 RUSSELL SENATE OFFICE BLDG, WASHINGTON DC 20510-2502	X	
HONORABLE CHARLES E. GRASSLEY, UNITED STATES SENATOR 135 HART SENATE OFFICE BLDG, WASHINGTON DC 20510-1501	X	
HONORABLE TOM HARKIN, UNITED STATES SENATOR 351 HART SENATE OFFICE BLDG, WASHINGTON DC 20510-1502	X	
HONORABLE CHARLES E. GRASSLEY, UNITED STATES SENATOR 206 FEDERAL BUILDING, 101 FIRST STREET, SE CEDAR RAPIDS, IA 52401	X	
HONORABLE CHARLES E. GRASSLEY, UNITED STATES SENATOR 721 FEDERAL BUILDING, 210 WALNUT STREET DES MOINES, IA 50309	X	
HONORABLE TOM HARKIN, UNITED STATES SENATOR 733 FEDERAL BUILDING, 210 WALNUT STREET DES MOINES IA 50309	X	
HONORABLE CHRISTOPHER BOND, UNITED STATES SENATOR 312 MONROE STREET, JEFFERSON CITY MO 65101	X	
HONORABLE JOHN C DANFORTH, UNITED STATES SENATOR 1233 JEFFERSON STREET, JEFFERSON CITY MO 65101	X	
HONORABLE JIM LEACH, HOUSE OF REPRESENTATIVES 1514 LONGWORTH HOUSE OFFICE BLDG, WASHINGTON DC 20515-1501	X	
HONORABLE HAROLD L. VOLKMER, HOUSE OF REPRESENTATIVES 2411 RAYBURN HOUSE OFFICE BLDG, WASHINGTON DC 20515-2509	X	
HONORABLE JIM LEACH, REPRESENTATIVE IN CONGRESS PARKVIEW PLAZA, ROOM 204, 107 EAST 2ND STREET OTTUMWA IA 52501	X	

• SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED

DISTRIBUTION -- EXTERNAL

REPORT NOTICE

HONORABLE HAROLD L VOLKMER, REPRESENTATIVE IN CONGRESS  
FEDERAL BUILDING-ROOM 370, 801 BROADWAY  
HANNIBAL, MO 63401-4353.

X

DIRECTOR, ADVISORY COUNCIL ON HISTORIC PRESERV  
OLD PO BLDG #809, 1100 PENNSYLVANIA AVENUE NW  
WASHINGTON DC 20004

X

DAVID COTTINGHAM-DIRECTOR, ECOLOGY & ENV CONS OFFICE  
DOC/NOAA/CS/EC - ROOM 6222, 14TH & CONSTITUTION AVENUE NW  
WASHINGTON DC 20230

X

DIRECTOR, OFFICE OF ENVIRONMENTAL COMPLIANCE  
DEPT OF ENERGY - ROOM 4G064, 1000 INDEPENDENCE AVE SW  
WASHINGTON DC 20585

X

DR ALLAN HIRSCH - DIRECTOR, OFFICE OF FEDERAL ACTIVITIES (A-104)  
US ENVIRONMENTAL PROTECTION AGENCY, 401 M STREET SW  
WASHINGTON DC 20460

X

OFFICE OF ENVIRONMENTAL PROJ REVIEW, DEPARTMENT OF INTERIOR  
MS 4239-M18, 18TH & C STREETS NW  
WASHINGTON DC 20240

12

DR DAVID CLAPP, OFFICE OF THE DIRECTOR  
CNTR FOR ENV HEALTH&INJ CONTROL/F 2, CENTERS FOR DISEASE CONTROL  
ATLANTA GA 30333

X

MR RICHARD NELSON - FIELD SUPRVR, U.S.FISH & WILDLIFE SERVICE  
1830 SECOND AVE. - 2ND FLOOR, ROCK ISLAND, IL 61201

;

DAVIS COUNTY ASCS OFFICE, PO BOX 160  
BLOOMFIELD IA 52537

X

DIVISION ADMINISTRATOR, FEDERAL HIGHWAY ADMINISTRATION  
PO BOX 627, 6TH AND KELLOGG STREET  
AMES IA 50010

X

FRED HAINLINE, SOIL CONSERVATION SERVICE  
106 N OODGE ST, BLOOMFIELD IA 52537

X

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED

DISTRIBUTION -- EXTERNAL

REPORT NOTICE

STATE CONSERVATIONIST, SOIL CONSERVATION SERVICE USDA 693 FEDERAL BLDG, 210 WALNUT STREET DES MOINES IA 50309	2
GEOLOGICAL SURVEY BUREAU, ENERGY AND GEOLOGICAL RESOURCES DIVN IOWA DEPT OF NATURAL RESOURCES, 123 NORTH CAPITOL STREET IOWA CITY IA 52240	X
WATER RES. RESEARCH CENTER, ATTN DR AL AUSTIN 355 TOWN ENGINEERING BUILDING, IOWA STATE UNIVERSITY AMES IA 50010	X
MR MORRIS KAY, ADMINISTRATOR US ENVIRON PROT AGENCY-REG VII, 726 MINNESOTA AVE KANSAS CITY KS 66101	3
MR JAMES C GRITMAN-REGIONAL DIRECTO, US FISH & WILDLIFE SERVICE FEDERAL BUILDING, FORT SNELLING TWIN CITIES MN 55111	X
LEWIS COUNTY ASCS OFFICE, PO BOX 98 MONTICELLO MO 63457	X
CLARK COUNTY ASCS OFFICE, PO BOX 165 KAHOKA MO 63445	X
SCOTLAND COUNTY ASCS OFFICE, PO BOX 336 MEMPHIS MO 63555	X
DIRECTOR, FEDERAL EMERGENCY MANAGEMENT AGENCY REGION VII, 911 WALNUT STREET - ROOM 300 KANSAS CITY MO 64106	X
REGIONAL ADMINISTRATOR, FEDERAL HIGHWAY ADMN - REG 7 PO BOX 19715, KANSAS CITY MO 64141	X
STATE DIRECTOR, FARMERS HOME ADMIN - USDA PARKDALE PLAZA, 555 VANDIVER DR - TERRACE LEVEL COLUMBIA MO 65201	X
MS. KATHY TORTORICI, US ENVIRON PROT AGENCY-REG VII, 726 MINNESOTA AVE, KANSAS CITY KS 66101	X

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED

DISTRIBUTION -- EXTERNAL

REPORT NOTICE

REGIONAL DIRECTOR, REGION VIII  
FEDERAL RAILROAD ADMINISTRATION, 2903 FEDERAL OFFICE BLDG  
KANSAS CITY MO 64106

X

OWIGHT SNEAD, SOIL CONSERVATION SERVICE  
ROUTE 1 - BOX 165, KAHOKA MO 63445

2

STATE CONSERVATIONIST, SOIL CONSERVATION SERVICE  
555 VANDIVER DRIVE, COLUMBIA MO 65201

2

COMMANDER, DEPARTMENT OF TRANSPORTATION  
SECOND COAST GUARD DISTRICT, 1430 OLIVE STREET  
ST LOUIS MO 63101

X

DISTRICT CHIEF - WRD, GEOLOGICAL SURVEY  
1400 INDEPENDENCE RD - MS 200, ROLLA MO 65401

X

REGIONAL FORESTER, FOREST SERVICE  
US DEPT OF AGRICULTURE, 310 W WISCONSIN AVE-SUITE 500  
MILWAUKEE WI 53203

2

HONORABLE TERRY BRANSTAD, GOVERNOR OF IOWA  
STATE CAPITOL, DES MOINES, IA 50319

X

MR STEVEN R MC CANN - DIRECTOR, IOWA DEPT OF ECONOMIC DEVELOPMENT  
DIVN OF COMMUNITY PROGRESS, 200 EAST GRAND  
DES MOINES IA 50319

4

HONORABLE JOHN ASHCROFT, GOVERNOR OF MISSOURI  
STATE CAPITOL, JEFFERSON CITY MO 65101

X

LOIS POHL - COORDINATOR, MO FED ASSISTANCE CLEARINGHOUSE  
TRUMAN BUILDING - ROOM 760, PO BOX 809  
JEFFERSON CITY MO 65102

4

MR LARRY WILSON - DIRECTOR, DEPT OF NATURAL RESOURCES  
WALLACE STATE OFFICE BLDG, 900 EAST GRAND AVENUE  
DES MOINES IA 50319

3

MR JAMES COBB, IOWA DEPT OF TRANSPORTATION  
826 LINCOLN WAY, AMES IA 50010

X

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED

DISTRIBUTION -- EXTERNAL

REPORT NOTICE

DIRECTOR, IOWA DEPT OF SOIL CONSERVATION  
WALLACE STATE OFFICE BLDG, 900 EAST GRAND AVENUE  
DES MOINES IA 50319

X

MR DAVID CROSSON, STATE HISTORIC PRESERVATION OFFICER  
BUREAU OF HISTORIC PRESERVATION, CAPITOL COMPLEX  
DES MOINES IA 50319

X

DIRECTOR, DIV OF COMMERCE & INDUSTRIAL DVLP  
PO BOX 118, 100 E CAPITOL  
JEFFERSON CITY MO 65101

X

CHARLES R MICHAEL-DIRECTOR, RIVER BASIN PLNG/POLICY UNIT  
DEPT OF NATURAL RESOURCES, PO BOX 176  
JEFFERSON CITY MO 65102

X

DIRECTOR, MISSOURI DEPT OF AGRICULTURE  
JEFFERSON BUILDING, JEFFERSON CITY MO 65102

X

MR GORDON FARABEE, MISSOURI DEPT OF CONSERVATION  
PO BOX 180, JEFFERSON CITY MO 65101

X

MR WILLIAM DEIFFENBACH, MISSOURI DEPT OF CONSERVATION  
PO BOX 180, JEFFERSON CITY MO 65101

X

MR ROBERT DOBBINS, MISSOURI DEPT OF CONSERVATION  
RR 1 BOX 198, ELSBERRY MO 63343

X

DIRECTOR, MISSOURI NATURAL RESOURCES COUNCIL  
PO BOX 176, JEFFERSON CITY MO 65101

X

ROBERT HUNTER - CHIEF ENGINEER, MISSOURI STATE HIGHWAY DEPT  
STATE HIGHWAY COMMISSION BLDG, PO BOX 270  
JEFFERSON CITY MO 65101

X

FREDERICK A BRUNNER PH.D P.E., STATE HISTORIC PRESERVATION OFCR  
DEPT OF NATURAL RESOURCES, PO BOX 176  
JEFFERSON CITY MO 65102

X

DIRECTOR, MISSOURI STATE PARK BOARD  
STATE OFFICE BUILDING, 1204 JEFFERSON  
JEFFERSON CITY MO 65101

X

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED

DISTRIBUTION -- EXTERNAL

	<u>REPORT</u>	<u>NOTICE</u>
HONORABLE DON E GETTINGS, IOWA SENATOR-33RD DISTRICT 513 LYNWOOD CIRCLE, OTTUMWA IA 52501	X	
HONORABLE JAMES MURPHY, MISSOURI SENATOR 3812 TESSON COURT, ST LOUIS MO 63123	X	
HONORABLE DANIEL JAY, IOWA REPRESENTATIVE-66TH DISTRICT 604 WILWOOD LANE, CENTERVILLE, IA 52544	X	
BOARD OF SUPERVISORS, DAVIS COUNTY COURT HOUSE BLOOMFIELD IA 52537	X	
COUNTY ATTORNEY, DAVIS COUNTY COURT HOUSE BLOOMFIELD IA 52537	X	
COUNTY CLERK, DAVIS COUNTY COURT HOUSE BLOOMFIELD IA 52537	X	
COUNTY ENGINEER, DAVIS COUNTY COURT HOUSE BLOOMFIELD IA 52537	X	
MIKE MCCLAIN, DAVIS COUNTY ENGINEER COURT HOUSE, BLOOMFIELD IA 52537	X	
ROBERT H BOATMAN, DAVIS COUNTY SOIL DIST ROUTE 1 - BOX 317, BLOOMFIELD IA 52537	X	
LAVERN WEILBRACHNER, DAVIS COUNTY SOIL DIST ROUTE 2, BLOOMFIELD IA 52537	X	
GERALD L FORSYTHE, DAVIS COUNTY SOIL DIST DRAKESVILLE IA 52552	X	
SHERRY BIRCHMIER, DAVIS COUNTY SOIL DIST R R 1, BLOOMFIELD IA 52537	X	
BOARD OF SUPERVISORS, CLARK COUNTY COURT HOUSE KAHOKA, MO 63445	X	
COUNTY ATTORNEY, CLARK COUNTY COURT HOUSE KAHOKA, MO 63445	X	

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED

DISTRIBUTION -- EXTERNAL

REPORT NOTICE

COUNTY CLERK, CLARK COUNTY COURT HOUSE KAHOKA; MO 63445	X
COUNTY ENGINEER, CLARK COUNTY COURT HOUSE KAHOKA, MO 63445	X
WAYNE J. BLUM, PRESIDING COMMISSIONER CLARK COUNTY COMMISSION, 111 EAST COURT KAHOKA MO 63445	5
BOARD OF JUDGES, LEWIS COUNTY COURT HOUSE MONTICELLO, MO 63457	X
CHAIRMAN, COUNTY BOARD OF SUPERVISORS COURT HOUSE, LEWIS COUNTY MONTICELLO, MO 63457	X
COUNTY ATTORNEY, COURT HOUSE LEWIS COUNTY, MONTICELLO, MO 63457	X
COUNTY CLERK, LEWIS CNTY COURT HOUSE MONTICELLO, MO 63457	X
LEWIS COUNTY HIGHWAY DEPT., MONTICELLO, MO 63457	X
BOARD OF SUPERVISORS, SCOTLAND COUNTY COURT HOUSE MEMPHIS MO 63474	X
COUNTY ATTORNEY, SCOTLAND COUNTY COURT HOUSE MEMPHIS MO 63474	X
COUNTY CLERK, SCOTLAND COUNTY COURT HOUSE MEMPHIS MO 63474	X
COUNTY ENGINEER, SCOTLAND COUNTY COURT HOUSE MEMPHIS MO 63474	X
MAYOR & CITY COUNCIL, CITY HALL BLOOMFIELD IA 52537	X

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED

DISTRIBUTION -- EXTERNAL

REPORT

NOTICE

DR LOREN N HORTON CHIEF, EDUCATIONAL AND COMMUNITY SERVICES  
IOWA STATE HISTORICAL DEPT., 402 IOWA AVENUE  
IOWA CITY IA 52240

X

PUBLIC LIBRARY, 107 N COLUMBIA  
BLOOMFIELD IA 52537

X

CANTON PUBLIC LIBRARY, CANTON MO 63435

X

EMILY H. SMITH, RI CNTY LEAGUE OF WOMEN VOTERS  
4428 42ND AVE., ROCK ISLAND, IL 61201

X

MR PAUL HANSEN, IZAAK WALTON LEAGUE  
MISSISSIPPI VALLEY REGNL OFFICE, 5701 NORMANDALE RD-SUITE 210  
MINNEAPOLIS MN 55424

X

MS JANE ELDER, THE SIERRA CLUB  
214 N HENRY ST SUITE 203, MADISON WI 53703

X

THE COURIER, 213 E 2ND ST  
OTTUMWA IA 52501

X

DAILY GATE CITY, BREHM COMMUNICATIONS INC  
1016 MAIN ST., PO BOX 528  
KEOKUK IA 52632

X

THE FAIRFIELD DAILY LEDGER, 112 E DROADWAY  
FAIRFIELD IA 52556

X

FORT MADISON DAILY DEMOCRAT, 1226 AVENUE H  
PO BOX 160, FORT MADISON IA 52627

X

THE HAWK EYE, 800 S MAIN  
PO BOX 10, BURLINGTON IA 52601

X

IOWEGIAN, 105 N MAIN ST  
CENTERVILLE IA 52544

X

NEWS, PO BOX 240  
215 W MCNROE, MT PLEASANT IA 52641-0240

X

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED



DISTRIBUTION -- EXTERNAL

	<u>REPORT</u>	<u>NOTICE</u>
CANTON PRESS-NEWS JOURNAL, CANTON, MO 63435		X
EXPRESS AND NEWS, EXPRESS PUBLISHING CO PO BOX 809, KIRSKVILLE MO 63501		X
HANNIBAL COURIER-POST, STAUFFER COMMUNICATIONS INC PO BOX A, 201 N THIRD ST HANNIBAL MO 63401		X
JOE ROBERTS - EDITOR, HOME TOWN JOURNAL MAIN STREET, KAHOKA MO 63445		X
THE LEWIS COUNTY JOURNAL, CANTON, MO. 63435		X
BATAVIA BEACON/FORUM, ELDON IA 52554		X
DEMOCRAT, 207-209 S MADISON P.O. BOX 19, BLOOMFIELD IA 52537		X
DONNELLSON STAR/WEST POINT BEE, PO BOX 340 CONNELLSON IA 52625		X
GATE CITY SHOPPERS FREE PRESS, BREHM COMMUNICATIONS INC 1016 MAIN ST, PO BOX 961 KEOKUK IA 52632		X
JOURNAL, 102 MAIN ST NEW LONDON IA 52645		X
VAN BUREN COUNTY LEADER-RECORD, PO BOX 155 FARMINGTON IA 52626		X
THE CRIER, BOX 1049 508 N MARION, KIRKSVILLE MO 63501		X
EXCELSIOR, BOX 250 LANCASTER MO 63548-0250		X
THE LA BELLE STAR, PO BOX 66 LA BELLE MO 63447		X

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED

## DISTRIBUTION -- EXTERNAL

HAZEL SMITH - EDITOR, MEDIA ADVISER  
MAIN STREET, KANSAS MO 63445

PALMYRA SPECTATOR, PO BOX 31  
PALMYRA MO 63461-0431

SENTINEL, MAIN AND MORGAN  
EDINA MO 63537

RADIO STATION KBIZ, 211 E 2ND ST  
OTTUMWA IA 52501

RADIO STATION KLEE, 212-1/2 E MAIN  
OTTUMWA IA 52501

RADIO STATION KQCA-FM, PO BOX 711  
HARRIBAL MO 63401-0711

PAUL DANKER, 2855 COLLEGE  
QUINCY IL 62301

NANCY GREER, 706 S HILLTOP DR  
QUINCY IL 62301

KEITH E AMSTUTZ, RR 1  
PULASKI IA 52584

R L BIRCHMIR, R1 - BOX 260  
MILTON IA 52570

OSCAR BUNTING, R1 - BOX 72  
PULASKI IA 52584

ALAN D GAFFNEY, RR1 - BOX 274  
MILTON IA 52570

J C GLASSCOCK, 902 CARROLL  
KEOKUK IA 52632

CULVER KLEIN, RR 1  
PULASKI IA 52584

REPORTNOTICE

X

X

X

X

X

X

X

X

X

X

X

X

X

X

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED

DISTRIBUTION -- EXTERNAL

BILL MATTHEWS, PULASKI IA 52584

VAUGHN WAGLER, RR 1  
PULASKI IA 52584

LAVERN WEILBRENNER, RR 2  
BLOOMFIELD IA 52537

OLEN WILLIER, RR 1  
PULASKI IA 52584

GERTRUDE BASH, RR 1 - BOX 82  
WILLIAMSTOWN MO 63473

LUDWIG BEACH, WILLIAMSTOWN MO 63473

LINDA BERTRAM, LURAY MO 63453

WAYNE BLUM, R 1 - BOX 220  
KAHOKA MO 63445

DAVID & PAM BOUDREAU, 574 E MAIN  
KAHOKA MO 63445

ESTON & JOANNE BOUDREAU, RR 3  
KAHOKA MO 63445

LLOYD & LINDA BOUDREAU, ROUTE Z  
CANTON MO 63435

ELDON BOURGEOIS, R1 - BOX 103  
WYACONDA MO 63474

RAY BOURGEOIS, ROUTE 1  
KAHOKA MO 63445

THOMAS & MARIE BRENNAN, WILLIAMTOWN MO 63473

EDWARD BREWER, R1 - BOX 73  
KAHOKA MO 63445

REPORT

NOTICE

X

X

X

X

X

X

X

X

X

X

X

X

X

X

X

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED

## DISTRIBUTION -- EXTERNAL

REPORTNOTICE

DELBERT & DOROTHY BROOKS, RR 3  
KAHOKA MO 63445

X

HAROLD CAMPBELL, RR 1  
ALEXANDRIA MO 63430

X

BRENDA J DANKER, ST PATRICK MO 63466

X

DAVID M DANKER, RR 2 - BOX 207A  
PERRYVILLE MO 63775

X

EMMA DANKER, ST PATRICK MO 63466

LUCILE DANKER, RR 3

X

KAHOKA MO 63445

EMMIT & HELEN DOBBINS, ST PATRICK MO 63466

X

GEORGE EVERMON, WYACONDA MO 63474

X

ALVA E FARR, R2 - BOX 72  
LAGRANGE MO 63448

X

R L FARR JR, R 2 - BOX 72  
LAGRANGE MO 63448

X

HAROLD & CELESTA GARES, 237 W MAPLE  
KAHOKA MO 63445

X

OVIE GLASSCOCK, 335 W COMMERCIAL  
KAHOKA MO 63445

X

WAYNE GUERNSEY, LURAY MO 63453

X

ROBERT & VERA HALL, WILLIAMTOWN MO 63473

X

HAROLD & MARILYN HALL, WILLIAMTOWN MO 63473

X

ROBERT HALL, BOX 73  
WILLIAMSTOWN MO 63473

X

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED

## DISTRIBUTION -- EXTERNAL

	<u>REPORT</u>	<u>NOTICE</u>
BUD HARDIN, 411 CONSTANCE DR CANTON MO 63435		X
JAMES & MARCIA HARDIN, 904 WHITE CANTON MO 63435		X
H HENRY HEINZE, RR 1 - BOX 76 WILLIAMSTOWN MO 63473		X
LELAND HOBSON, PO BOX 4 KAHOKA MO 63445		X
W W HODGES, R1 - BOX 56 KAHOKA MO 63445		X
KAY A HOLMES, RR 3 KAHOKA MO 63445		X
LESTER HOPP, LURAY MO 63453		X
EMIL L HUMES, ROUTE 1 WYACONDA MO 63474		X
JOE A HUMES, WYACONDA MO 63471		X
ERNEST HUMES, BOX 109 WYACONDA MO 63474		X
HARLAN E HUNZIKER, RR 3 KAHOKA MO 63445		X
LERROY & GERALDINE HUNZIKER, RR 3 KAHOKA MO 63445		X
GARY H HUNZIKER, ROUTE 3 KAHOKA MO 63445		X
ROBERT KINKADE, ROUTE 1 - BOX 70 KAHOKA MO 63445		X

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED

DISTRIBUTION -- EXTERNAL

ARNOLD KIRCHNER, WYACONDA MO 63474  
 BILL & JANET KIRCHNER, ST PATRICK MO 63466  
 CLARENCE KIRCHNER, ST PATRICK MO 63466  
 JOHN & MARIE KIRCHNER, CANTON MO 63435  
 NANCY L KIRCHNER, ST PATRICK MO 63466  
 NICHOLAS KIRCHNER, ST PATRICK MO 63466  
 KENNETH KIRCHNER, R 3 - BOX 138  
 KAHOKA MO 63445  
 WARREN & ROSA KRAUS, LURAY MO 63453  
 ROBERT LAFRENZ, RR1 - BOX 102  
 WYACONDA MO 63474  
 ANNA LOGSDON, ST PATRICK MO 63466  
 JEFF LOGSDON, RR 3  
 KAHOKA MO 63455  
 LARRY LOGSDON, ST PATRICK MO 63466  
 LARRY E LOGSDON, ST PATRICK MO 63466  
 LAVETA LOGSDON, ST PATRICK MO 63466  
 LYNN LOGSDON, ST PATRICK MO 63466  
 ROBIN LOGSDON, RR 3  
 KAHOKA MO 63445  
 WAYNE MEINHARDT, LURAY MO 63453  
 GARY MEINHARDT, RR #1 - BOX 45A  
 KAHOKA MO 63445

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED

REPORT

NOTICE

X  
 X  
 X  
 X  
 X  
 X  
  
 X  
  
 X  
 X  
  
 X  
 X  
 X  
 X  
 X  
 X  
 X  
 X

DISTRIBUTION -- EXTERNAL

REPORT

NOTICE

AUGUST R MOELLER, ST PATRICK MO 63466

X

JOHN & JEANNE NICHOLS, CANTON MO 63435

X

LEO & CATHERINE NICHOLS, RR 1  
CANTON MO 63435

X

RICHARD O'BRIEN, RR1 - BOX 69  
ARBELA MO 63432

X

JOHN PARKER, RR 2  
LURAY MO 63453

X

WESLEY PERRY, ROUTE 2 - BOX 2  
WYAONDA MO 63474

X

FORREST PHILLIPS, 865 W ELM  
KAHOKA MO 63445

X

GENE PHILLIPS, RR 1 - BOX 80A  
LURAY MO 63453

X

KEITH PHILLIPS, RR 1 - BOX 192  
KAHOKA MO 63445

X

HENRY PLENCE, ROUTE 1 - BOX 200  
KAHOKA MO 63445

X

JOHN PLENCE, ROUTE 1 - BOX 200  
KAHOKA MO 63445

X

RALPH PLENCE SR, ROUTE 1 - BOX 22  
KAHOKA MO 63445

X

SCOTT E RICHMOND, ST PATRICK MO 63466

X

SHAWN RICHMOND, ST PATRICK MO 63466

X

WILLIAM & NORMA RICHMOND, ST PATRICK MO 63466

X

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED

DISTRIBUTION -- EXTERNAL

REPORT

NOTICE

LARRY ROSS, RR 3  
KAHOKA MO 63445

RON & JANET RYAN, ST PATRICK MO 63466

GERALD & CARMELITA SCHUTTE, RR 3  
KAHOKA MO 63445

HERBERT E SCHUTTE, RR 3  
KAHOKA MO 63445

JOE B SCHUTTE, RR  
LAGRANGE MO 63451

PAUL & CATHERINE SCHUTTE, RR 3  
KAHOAK MO 63445

CHARLES SELWAY, RR 1 - BOX 47  
WILLIAMSTOWN MO 63473

JIM & PAULINE SHAFFER, RR 3  
KAHOKA MO 63445

HAROLD TRUMP, BOX 124  
LURAY MO 63453

BRUCE & MELODY UHLMMEYER, RR 3  
KAHOKA MO 63445

ERVIN & NANCY UHLMMEYER, RR 1  
ALEXANDRIA MO 63430

GREG UHLMMEYER, CANTON MO 63435

JUNIOR & MAXINE UHLMMEYER, RR 1  
CANTON MO 63435

KENNETH UHLMMEYER, ROUTE 1 - BOX 59  
CANTON MO 63435

X  
X  
X  
X  
X  
X  
X  
X  
X  
X  
X  
X  
X  
X  
X  
X  
X  
X  
X  
X  
X

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED



DISTRIBUTION -- EXTERNAL

ROVENA UHLMAYER, CANTON MO 63435  
 WALTER & ROSALINE UHLMAYER, RR 1  
 CANTON MO 63435  
 EDWARD K VANCE, RR  
 REVERE MO 63465  
 C G WAPLES, RR 1  
 ALEXANDRIA MO 63430  
 DEAN WEBSTER, RR 3  
 KAHOKA MO 63445  
 JOE M WHEELER, CANTON MO 63435  
 SAM & MARY JEAN WHEELER, ROUTE 1 - BOX 83  
 WILLIAMSTOWN MO 63473  
 HUGH WILSON, WYACONDA MO 63471  
 TERRY WINTERS, ROUTE 1  
 CANTON MO 63435  
 MR & MRS M F DOMBROWSKI, 524 N LONGFELLOW ST  
 ARLINGTON VA 22203

REPORT

NOTICE

X  
 X  
 X  
 X  
 X  
 X  
 X  
 X  
 X  
 X

\*SINGLE COPIES DISTRIBUTED EXCEPT AS INDICATED

DISTRIBUTION -- INTERNAL (All receive Report)

COMMANDER, US ARMY ENGINEER DISTRICT, ROCK ISLAND,  
 CLOCK TOWER BLDG., ROCK ISLAND, IL 61204-2004

ATTN: CENCR-DE CENCR-ED-C CENCR-PD-W  
 CENCR-RE CENCR-PA CENCR-CD  
 CENCR-ED CENCR-PD (2) CENCR-OD  
 CENCR-ED-D CENCR-PD-C CENCR-OD-S  
 CENCR-ED-DG CENCR-PD-E CENCR-IM-C (3)  
 CENCR-ED-H